


N O T I C E


THIS DOCUMENT HAS BEEN REPRODUCED FROM
MICROFICHE. ALTHOUGH IT IS RECOGNIZED THAT
CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE AS MUCH
INFORMATION AS POSSIBLE



(NASA-CR-164684) A PROGRAM TO EVALUATE A
CONTROL SYSTEM BASED ON FEEDBACK OF
AERODYNAMIC PRESSURE DIFFERENTIALS, PART 1
Interim Report (Kansas Univ. Center for
Research, Inc.) 213 p HC A10/MF A01

N81-30134

G3/06 27182
Unclas



THE UNIVERSITY OF KANSAS CENTER FOR RESEARCH, INC.

2291 Irving Hill Drive—Campus West
Lawrence, Kansas 66045

Prepared under
NASA Grant No. NAG 4-5

Interim Report
for
A PROGRAM TO EVALUATE A CONTROL SYSTEM
BASED ON FEEDBACK OF AERODYNAMIC
PRESSURE DIFFERENTIALS

KU-FRL-490-1

Part I

Prepared by: Ronald R. Hrabak
David W. Levy
Paul Finn

Principal Investigator: Jan Roskam

University of Kansas Flight Research Laboratory
Lawrence, Kansas 66044
August 1981

ABSTRACT

This report describes work done under a program to evaluate the use of pressure differentials in a flight control system.

The first part of the program consists of a study to determine the pressure profile around the test surface. This study was performed using two techniques:

- 1) Windtunnel Data (Actual)
- 2) NASA/Langley Single Element Airfoil Computer Program (Theoretical).

The system designed to evaluate the concept of using pressure differentials is composed of a sensor drive and power amplifiers, actuator, position potentiometer, and a control surface.

The second part of this program consists of determining the characteristics (both desired and actual) of the system and each individual component. This report, however, terminates with the desired characteristics of the system as a whole. The actual frequency response of the system could not be obtained due to the use of an inappropriate sensor.

This report describes the flight control system developed, the testing procedures and data reduction methods used, and theoretical frequency response analysis.

TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| ABSTRACT. | i |
| TABLE OF CONTENTS | iii |
| LIST OF SYMBOLS | vii |
| LIST OF FIGURES | ix |
| LIST OF TABLES. | xi |
| | |
| 1. INTRODUCTION. | 1 |
| 1.1 PURPOSE. | 1 |
| 1.2 BACKGROUND | 1 |
| 1.3 METHODOLOGY. | 2 |
| 2. SYSTEM DESCRIPTION. | 3 |
| 2.1 OVERALL SYSTEM THEORY. | 3 |
| 2.2 COMPONENT BREAKDOWN. | 3 |
| 2.2.1 SENSOR. | 6 |
| 2.2.2 SIGNAL CONDITIONER. | 6 |
| 2.2.3 DRIVE AMPLIFIER | 8 |
| 2.2.4 POWER AMPLIFIER | 10 |
| 2.2.5 ACTUATOR. | 12 |
| 2.2.6 POSITION POTENTIOMETER. | 12 |
| 2.2.7 SURFACE AND MOUNTING HARDWARE | 12 |
| 3. PHASE I: PRESSURE PROFILE STUDY. | 15 |
| 3.1 PURPOSE. | 15 |
| 3.1.1 BASELINE DATA ON PRESSURE DISTRIBUTION. | 15 |
| 3.1.2 SENSOR LOCATION | 15 |
| 3.1.3 SENSOR RANGE. | 16 |

TABLE OF CONTENTS (continued)

| | <u>Page</u> |
|--|-------------|
| 3.2 FACILITIES AND HARDWARE. | 16 |
| 3.2.1 WINDTUNNEL. | 16 |
| 3.2.2 TEST SURFACE. | 18 |
| 3.3 TEST SET-UP. | 18 |
| 3.4 PROCEDURES | 18 |
| 3.5 DATA PROCESSING. | 19 |
| 3.5.1 DATA CORRECTIONS. | 19 |
| 3.5.2 DATA REDUCTION. | 20 |
| 3.6 RESULTS AND DISCUSSION | 21 |
| 4. PHASE II: SENSOR CALIBRATION | 23 |
| 4.1 PURPOSE. | 23 |
| 4.2 FACILITIES AND HARDWARE. | 23 |
| 4.2.1 FACILITIES. | 23 |
| 4.2.2 HARDWARE. | 23 |
| 4.3 TEST SET-UP. | 27 |
| 4.4 PROCEDURES | 27 |
| 4.5 RESULTS AND DISCUSSION | 29 |
| 4.6 MODIFICATIONS AND SUBSEQUENT RESULTS | 30 |
| 4.6.1 SENSOR PORT DIAMETER. | 30 |
| 4.6.2 AMPLIFIER GAIN. | 30 |
| 4.6.3 AMPLIFIER VOLTAGE | 31 |
| 4.6.4 MIDDLE THERMISTOR | 31 |
| 4.7 CONCLUSIONS AND RECOMMENDATIONS. | 31 |
| 5. PHASE III: FREQUENCY RESPONSE. | 33 |
| 6. THEORETICAL ANALYSIS. | 37 |

TABLE OF CONTENTS (continued)

| | <u>Page</u> |
|---|-------------|
| 6.1 THEORETICAL PRESSURE DISTRIBUTION. | 37 |
| 6.2 CLOSED LOOP DYNAMIC STABILITY ANALYSIS | 42 |
| 7. CONCLUSIONS AND RECOMMENDATIONS | 51 |
| 8. REFERENCES. | 53 |
| APPENDICES: | |
| A. PRESSURE PROFILE SENSITIVITY PLOTS. | 55 |
| A.1 FLAP DEFLECTION. | 57 |
| A.2 ANGLE OF ATTACK. | 71 |
| B. PRESSURE TRANSDUCER CALIBRATION PROGRAM | 85 |
| C. THEORETICAL PRESSURE PROFILE DATA | 87 |
| C.1 SAMPLE LISTING OF SEAP OUTPUT. | 89 |
| C.2 PRESSURE DISTRIBUTION DATA AS INPUT TO HP9825 A. | 93 |
| C.3 INTERPOLATED CHANGE IN C_p --BY ANGLE OF ATTACK AND FLAP DEFLECTION. | 111 |
| C.4 INTERPOLATED CHANGE IN C_p --BY TAP LOCATION | 129 |
| C.5 GRAPHICAL OUTPUT--FLAP DEFLECTION SENSITIVITY. | 145 |
| C.6 GRAPHICAL OUTPUT--ANGLE OF ATTACK SENSITIVITY. | 159 |
| C.7 NUMERICAL REGRESSION DATA. | 173 |
| D. THEORETICAL FREQUENCY ANALYSIS DATA | 187 |
| D.1 LOW DYNAMIC PRESSURE | 188 |
| D.1.1 WITH PRESSURE SENSOR (PRESSURE COMMAND) | 190 |
| D.1.2 WITHOUT PRESSURE SENSOR (POSITION COMMAND). | 193 |
| D.2 HIGH DYNAMIC PRESSURE. | 196 |

TABLE OF CONTENTS (continued)

| | <u>Page</u> |
|--|-------------|
| D.2.1 WITH PRESSURE SENSOR (PRESSURE COMMAND) | 198 |
| D.2.2 WITHOUT PRESSURE SENSOR (POSITION COMMAND) | 201 |

LIST OF SYMBOLS AND ACRONYMS

| <u>Symbol</u> | <u>Definition</u> | <u>Dimension</u> |
|-------------------|---|-----------------------|
| C_p | Pressure coefficient | |
| q | Dynamic pressure | lbs, ft ⁻² |
| α | Angle of attack | deg |
| θ | Euler pitch angle | deg |
| δ_E | Elevator angle | deg |
| $\omega_{n_{sp}}$ | Undamped natural frequency of the short period mode | Hz |
| ω_{n_p} | Undamped natural frequency of the dutch roll mode | |
| ΔP | Change in pressure between lower and upper surface | lbs, ft ⁻² |

Acronyms

| | |
|------|---|
| DAS | Data Acquisition System |
| AFCS | Automatic Flight Control System |
| SEAP | Single Element Airfoil Program |
| SSSA | Separate Surface Stability Augmentation |

LIST OF FIGURES

| <u>Figure</u> | <u>Title</u> | <u>Page</u> |
|---------------|---|-------------|
| 2.1 | System Block Diagram. | 4 |
| 2.2 | System Flow Diagram | 5 |
| 2.3 | Differential Pressure Sensor. | 5 |
| 2.4 | Sensor Circuit Schematic. | 7 |
| 2.5 | Signal Conditioner Schematic. | 7 |
| 2.6 | Drive Amplifier Schematic | 9 |
| 2.7 | Power Amplifier Schematic | 11 |
| 2.8 | Solactor Actuator Properties. | 11 |
| 2.9 | Test Surface and Mounting Hardware. | 13 |
| 2.10 | Test Surface (Assembly View). | 13 |
| 3.1 | Manometer Board | 17 |
| 3.2 | Test Surface in Wind Tunnel | 17 |
| 4.1 | 2012 Data Acquisition System. | 24 |
| 4.2 | HP9825A Computer and 9872 Plotter | 24 |
| 4.3 | Data Acquisition System Schematic | 25 |
| 4.4 | Pressure Sensor Calibration Mount | 26 |
| 4.5 | Calibration Schematic | 26 |
| 4.6 | Sensor Calibration Curve. | 28 |
| 5.1 | Response to a Step Input. | 34 |
| 6.1 | Delta P Airfoil Section | 38 |
| 6.2 | Airfoil with Flap Deflections | 39 |
| 6.3 | System Block Diagram (Pressure Command) | 43 |
| 6.4 | System Block Diagram (Position Command) | 43 |

LIST OF FIGURES (continued)

| <u>Figure</u> | <u>Title</u> | <u>Page</u> |
|---------------|---|-------------|
| 6.5 | Pitch Attitude Hold for Airplane A (App. C., Ref. 4) with Pressure Sensor (q = 8.5 psf) | 45 |
| 6.6 | Pitch Attitude Hold for Airplane A (App. C., Ref. 4) with Pressure Sensor (q = 76.3 psf). | 46 |
| 6.7 | Pitch Attitude Hold for Airplane A (App. C., Ref. 4) (q = 8.5 psf). | 47 |
| 6.8 | Pitch Attitude Hold for Airplane A (App. C., Ref. 4) (q = 76.3 psf) | 48 |

LIST OF TABLES

| <u>Table</u> | <u>Title</u> | <u>Page</u> |
|--------------|---|-------------|
| 2.1 | Delta P Drawings Guide. | 3 |
| 2.2 | Signal Conditioner Test Points and Input Terminals | 8 |
| 2.3 | Delta P Surface and Hardware Drawings | 14 |
| 3.1 | Pressure Profile Run Log. | 19 |
| 4.1 | Calibration Run Data. | 29 |
| 5.1 | Part A Run Schedule | 33 |
| 5.2 | Part B Run Schedule | 34 |
| 5.3a | Frequency Response Test Runs--Position. | 36 |
| 5.3b | Frequency Response Test Runs--Pressure. | 36 |
| 6.1 | Delta P Airfoil Coordinates | 40 |
| 6.2 | Surface Coordinates at Different Flap Deflections | 40 |

1. INTRODUCTION

1.1 PURPOSE

The purpose of this study is to provide information leading to determining the feasibility of using a differential pressure feedback signal in an airplane's flight control system.

1.2 BACKGROUND

In nearly all airplanes equipped with automatic flight controls (AFC), the control surfaces are positioned via a feedback loop with a feedback gain proportional to control surface position. Since in many instances control surface position is linearly related to the differential pressure created by a control surface deflection, this type of feedback works well.

However, in many systems, it is found necessary to schedule the feedback gain as a function of flight attitude, Mach number, dynamic pressure, or a combination thereof. (At this point in time, Mach number is not included.)

Since the purpose of any control motion is to create a certain pressure differential, it is logical to consider a system whereby control surface motion is signalled by a gain directly proportional to the pressure differential. The differential itself would then have to be sensed by a suitable pressure sensor.

This method of control surface signalling may simplify control law requirements. It may also allow for the direct control of airplane attitude relative to the total velocity vector of an

airplane. This is because such attitudes are themselves proportional to pressure differentials across lifting surfaces (Reference 1).

1.3 METHODOLOGY

This study was performed using the following three phases:

- 1) Pressure profile study
- 2) Sensor calibration
- 3) Frequency response and transfer function determination.

The pressure profile study is used to determine the range and characteristics of the test surface. The sensor calibration phase is needed to obtain the sensor's physical characteristics. (The actual work of this study terminated at this phase.) A theoretical frequency response analysis has been conducted; but at the time of this report, the physical testing of this phase has not begun, due to the results of Phase II.

2. SYSTEM DESCRIPTION

2.1 OVERALL SYSTEM THEORY

The flight control system which was designed to test the use of a differential pressure sensor is illustrated in Figure 2.1. The block diagram is a pitch attitude hold system with the differential pressure feedback for the $\delta_{E_{COMM}}$ loop. The flow diagram of the inner loop is illustrated in Figure 2.2.

2.2 COMPONENT BREAKDOWN

The components used in the testing are listed in the flow diagram of Figure 2.2 and can be found in the appropriate drawings according to Table 2.1.

Table 2.1 Guide to Delta P Drawings

| Drawing No.(s) | Component |
|-----------------|--|
| DP-0105 | Sensor |
| DP-0204 | Sensor Circuit Schematic |
| DP-0204 | Sensor Wiring Diagram and Layout |
| DP-0301 | Signal Conditioner (Control Box) |
| DP-0204 | Signal Conditioner Schematic |
| DP-0204 | Signal Conditioner Wiring Diagram and Layout |
| DP-0301 | Drive Amplifier |
| DP-0301 DP-0203 | Power Amplifier |
| DP-0203 | Power Amplifier Schematic |
| DP-0101 | Actuator (Assembly View) |
| DP-0101 | Position Potentiometer (Assembly View) |
| DP-0101 | Delta P Test Surface (Assembly View) |




Figure 2.1 System Block Diagram




Figure 2.2 System Flow Diagram




Figure 2.3 Differential Pressure Sensor

2.2.1 SENSOR

The sensor used in this study was designed by Jim Black, NASA DFRC Engineer. The sensor uses three thermistors to measure the differential pressure between the two ports. Figure 2.3 illustrates the sensor's components. The circuit diagram for the sensor is found in Figure 2.4.

The sensor, designed to be used in a wing-leveler autopilot system, operates by keeping the middle thermistor at a constant temperature. As the air flows past the front thermistor (a flow due to differential pressure), it is cooled. After passing the middle thermistor, the air is heated, thus causing the rear thermistor to be at a different temperature. This temperature difference results in a voltage difference within the sensor circuit. This difference, again, is the result of a pressure differential.

2.2.2 SIGNAL CONDITIONER

The signal conditioner in the flow diagram performs the following tasks:

- 1) Reads the differential pressure signal from the sensor-circuit combination
- 2) Monitors the position of the control surface.

The signal conditioner uses the signal from the position potentiometer to prevent a hardover condition.

The circuit diagram for the signal conditioner is given in Figure 2.5. The signal conditioner (designed by Dr. D. G. Daugherty,




Figure 2.4 Sensor Circuit Schematic




Figure 2.5 Signal Conditioner Schematic

KU Electrical Engineering Professor) was also designed to aid the frequency response testing of Phase III. To do this, test points and input terminals were included; their functions are listed in Table 2.2.

Table 2.2 Signal Conditioner Test Points and Input Terminals

| Circuit Point No. | Symbol | Function |
|-------------------|----------------------|---|
| 1 | +P (OUT) | Differential Pressure Output Signal |
| 2 | $-P_c$ (IN) | Frequency Response Signal Input |
| 3 | $P_c - P = \epsilon$ | Error Signal |
| 4 | Comp. | Compensating Circuit Signal (if Required) |
| 5 | P.C. | Position Command Signal-Sensor can be bypassed and surface controlled using position potentiometer (LVDT) |

2.2.3 DRIVE AMPLIFIER

The drive amplifier used in this study is from the NASA M99 separate Surface Stability Augmentation (SSSA) Project. The schematic of the drive amplifier may be found in Figure 2.6.

The drive amplifier uses standard op-amp methods for developing opposite phase drive signals required by the power amplifier. Discrete transistors connected as complementary emitter-followers provide the necessary drive current for the power amplifier inputs. Small (56 Ω) resistors are included in the collector circuits of




Figure 2.6 Drive Amplifier Schematic (Reference 2)

these emitter-followers as protection against mishaps during circuit testing. In normal circuit operation their function is inconsequential (Reference 2).

The drive amplifier receives the V_{IN} signal from the signal conditioner, while also monitoring the position of the surface through the V_{XS} terminal. The output then goes to the power amplifier.

2.2.4 POWER AMPLIFIER

The power amplifier used in this study is also from the SSSA project. The schematic of the power amplifier is given in Figure 2.7.

The power amplifier is a Class-B push-pull bridge configuration. This configuration was used in order to attain actuator voltages approaching ± 28 volts (56 volts, peak-to-peak). Diodes are included for protecting the power transistors against inductive spikes from the actuator (Reference 2).

The power amplifier receives four (4) signals from the drive amplifier:

- 1) A FDBK
- 2) A IN
- 3) B FDBK
- 4) B IN

The A and B FDBK signals are transmitted directly to the actuator. It is these signals which drive the actuator. The A and B IN signals originate at the drive amplifier. The A and B IN signals are connected to the drive amplifiers A and B OUT terminals, respectively.





Figure 2.7 Power Amplifier Schematic



NOTE: 28 VDC OPERATION, 25°C

Figure 2.8 Solactor Actuator Properties

2.2.5 ACTUATOR

The actuator used in this study is the McDonnell Douglas "Solactor," Model 6023 A, also used in the SSSA project. The properties of the actuator are given in Figure 2.8.

2.2.6 POSITION POTENTIOMETER

The position potentiometer (L.V.D.T.) used in this study has the following characteristics:

- 1) Type: III
- 2) Resistance: $2K \Omega \pm 10\%$
- 3) Range: 3" linear: 1%

2.2.7 SURFACE AND MOUNTING HARDWARE

The test surface used in this study is the Beech, Model 60 (DUKE), elevator-trim tab assembly. The surface was obtained through the Aerospace Engineering Department at the University of Kansas. The surface and mounting hardware are illustrated in Figures 2.9 and 2.10. Also included in these figures are the actuator and L.V.D.T. Table 2.3 gives a listing of the detailed drawings of the surface and mounting hardware which are available through the Flight Research Lab, at the University of Kansas Center for Research, Inc.





Figure 2.9 Test Surface and Mounting Hardware



ORIGINAL PAGE IS
OF POOR QUALITY

Figure 2.10 Test Surface (Assembly View)

Table 2.3 Delta P Surface and Hardware Drawings

| Drawing No. | Item |
|-------------|------------------------------|
| DP-0101 | Test Surface (Assembly View) |
| DP-0102 | Potentiometer Clevis |
| DP-0102 | Actuator Clevis |
| DP-0102 | Windtunnel Mount |
| DP-0102 | Mounting Rib |
| DP-0103 | Aft Actuator Mount |
| DP-0103 | Fore Actuator Mount |
| DP-0104 | Endplate Mount |
| DP-0104 | Endplate |

3. PHASE I: PRESSURE PROFILE STUDY

3.1 PURPOSE

3.1.1 BASELINE DATA ON PRESSURE DISTRIBUTION

Because of the uniqueness of the airfoil used, a pressure profile study is necessary to obtain baseline data on the pressure distribution at specific angles of attack and flap deflections. The data obtained during this study are used against the theoretical analysis of Section 6.1. If the pressure distribution can be predicted, then a windtunnel pressure profile study can be eliminated.

3.1.2 SENSOR LOCATION

The major objective of the pressure profile study is to determine the location of the differential pressure sensor.

The control system illustrated in Figure 2.2 is designed primarily for flap deflection sensitivity; however, provisions have been made in the signal conditioner control box for angle of attack sensitivity. The selection can be made through a switch mounted on the control box.

The locations of the sensors are determined using the results of the data reduction. These results are best summarized using the graphs found in the data presentation of this report. These graphs show how the change in the pressure coefficient, $\Delta C_p = C_{p_{\text{LOWER}}} - C_{p_{\text{UPPER}}}$, changes with angle of attack and flap deflections for 13 chordwise locations.

The criteria for selection are as follows:

- Sensor No. 1: a) Sensitivity to angle of attack
b) Least sensitivity to flap deflection
c) Consistent linearity

- Sensor No. 2: a) Least sensitivity to angle of attack
b) Sensitivity to flap deflection
c) Consistent linearity

With sensors at these two locations, both angle of attack and flap deflection can be sensed separately and accurately within the range of linear aerodynamics.

3.1.3 SENSOR RANGE

Results from the pressure profile study are also used to determine the range of pressure required to be sensed by the sensor. It is this characteristic which the sensor does not have.

3.2 FACILITIES AND HARDWARE

3.2.1 WINDTUNNEL

All testing of the surface was performed at the University of Kansas Aerospace Engineering Department's 3' x 4' subsonic windtunnel. Facilities include a 60 tube manometer, 26 of which were used for this study. The manometer may be seen in Figure 3.1. Figure 3.2 views the test surface before a run.




Figure 3.1 Manometer Board




Figure 3.2 Test Surface in Wind Tunnel

3.2.2 TEST SURFACE

Provisions were made on the test surface of Figure 3.2 to measure the pressure profile at 13 different locations, on each side of the surface. All static ports were connected to the manometer board using 1/16" I.D. pressure tubing. All connections were made airtight using a polyurethane spray lacquer.

3.3 TEST SET-UP

The test set-up consisted of installing the surface in the windtunnel, and connecting the pressure lines to the appropriate connectors on the manometer board. Each pressure line was tested for blockages and leaks. When all lines were determined to be clear and airtight, the testing began. The manometer board was tilted at a 30° angle to match the inclination of the tunnel pitot-static manometer; this simplifies the data reduction.

A static pressure port was installed in the tunnel test section. The port was used for a reference static pressure on the manometer board. Corrections due to position are outlined in Subsection 3.5.1.

3.4 PROCEDURES

The procedures for the pressure profile testing followed the items of Table 3.1. A total of nine runs were performed. Each run consisted of the following steps:

- 1) Setting flap at desired deflection
- 2) Setting tunnel at desired dynamic pressure

- 3) Obtaining equilibrium condition in manometer board tubes
- 4) Setting surface at minimum angle of attack (-8°)
- 5) Reading manometer board pressure tubes
- 6) Repeating Steps (3) and (5) for angles of attack -8° to $+8^\circ$ by increments of 2.

Table 3.1 Pressure Profile Run Log

| Run No. | α | δ_F (deg) |
|---------|---------------------------|------------------|
| 1 | α_{SWEEP}^* | - 20 |
| 2 | | - 15 |
| 3 | | - 10 |
| 4 | | - 5 |
| 5 | | 0 |
| 6 | | + 5 |
| 7 | | + 10 |
| 8 | | + 15 |
| 9 | | + 20 |

* α_{SWEEP} : -8, -6, -4, -2, 0, +2, +4, +6, +8 (degrees)

Note: All testing was performed for a tunnel dynamic pressure of 25.6 psf.

3.5 DATA PROCESSING

3.5.1 DATA CORRECTIONS

The raw data obtained from the Phase I testing includes:

- 1) Static pressure at the 26 locations along the test surface (P_s)
- 2) Static pressure in the test section (P_∞)
- 3) Dynamic pressure at the test section (q)

These values, in centimeters of alcohol, are read from the manometer board, inclined to 30°. Before the data can be reduced, two corrections must be made. First, the dynamic pressure must also be corrected for tunnel blockage. The procedure of Pope (Reference 3) is followed. Second, the test section static pressure port (see Figure 3.3), being located forward of the test surface leading edge, reads slightly high due to the increase in dynamic pressure over the surface from tunnel blockage. The incompressible Bernoulli equation is used to calculate the true reference static pressure from the change in dynamic pressure due to blockage.

The corrections are detailed in Part II of this report, which contains all the data obtained from the pressure profile study. Included in Part II are sample calculations, computer program listings, and presentations (tabular and graphical) of the data.

3.5.2 DATA REDUCTION

Since the inclination of the manometer board (used to measure the test surface's static pressure) is identical to the dynamic pressure manometer tube, the coefficient of pressure is calculated directly from:

$$C_p = \frac{P_s - P_\infty}{q} \quad (3.1)$$

where the pressures have been corrected as per Subsection 3.5.1. Since differential pressure is the quantity to be investigated, the difference between the lower and upper coefficients is calculated. However, the lower and upper pressure tap locations are not the same. Therefore, the lower surface pressure coefficients are linearly interpolated to the upper surface tap locations.

It is desired to find the chordwise locations that satisfy the criteria specified in Subsection 3.1.2. Toward this end, the change in pressure coefficient, $C_{P_{\text{LOWER}}} - C_{P_{\text{UPPER}}}$, is plotted against flap deflection and angle of attack for each of the 13 chordwise tap locations. (These graphs are located in Appendix A and in Part II.) This facilitates inspection and interpretation of the data. A numerical regression of the data is performed to quantify the slopes of these graphs. This augments the interpretation of the figures and is used in the theoretical analysis of Section 6.2.

3.6 RESULTS AND DISCUSSION

Based on the figures of Appendix A, tap number (13) ($x/c = .766$) has the best combination of linear sensitivity to flap deflection, and insensitivity to angle of attack. One pressure sensor, located here, can sense flap position with little error to angle of attack. The location of tap number (1) is best for angle of attack sensitivity, but is not used for the purpose of this study.

The required range of the sensor is best put in terms of pressure coefficient:

$$-1.2 \leq \Delta C_p \leq 1.2 \quad (3.2)$$

This is the nondimensional differential pressure occurring at the largest angle of attack and flap deflection tested. At a dynamic pressure of $q = 25$ psf, the required range is:

$$-30 \leq \Delta P \leq +30 \text{ psf} \quad (3.3)$$

If this study is to be repeated, it is recommended that a more common airfoil, with a known, experimental pressure distribution be used. For example, a NACA 0012 would be a good choice because of its wide use in horizontal tails.

4. PHASE II: SENSOR CALIBRATION

4.1 PURPOSE

The sensor calibration process is performed to determine the relationship between the differential pressure acting on the sensor, and its output. From this process the drive amplifier's gain value is determined.

4.2 FACILITIES AND HARDWARE

4.2.1 FACILITIES

The calibration tests were performed using the windtunnel facilities previously mentioned in Section 3.2. Also included in the facilities is the Hewlett Packard (HP) 2012 Data Acquisition System (DAS), HP9825 micro-minicomputer, and the HP9872 X-Y plotter, all shown in Figures 4.1 and 4.2. A schematic of the entire data acquisition system is illustrated in Figure 4.3.

4.2.2 HARDWARE

The hardware and components used for the calibration tests included:

- 1) Differential pressure sensor
- 2) Sensor calibration mount
- 3) Signal conditioner

The calibration mount is shown in Figure 4.4. The mount provides a pitot-static pressure differential across the sensor which is




Figure 4.1 2012 Data Acquisition System





Figure 4.2 HP9825 A Computer and 9872 Plotter



HP-2012 Data Acquisition System

Figure 4.3 Data Acquisition System Schematic




Figure 4.4 Pressure Sensor Calibration Mount




Figure 4.5 Calibration Schematic

calibrated against the tunnel manometer. The apparatus utilizes a "u" shaped windtunnel mount to secure it in the tunnel.


4.3 TEST SET-UP

The schematic of Figure 4.5 illustrates the uses of the components for the calibration process. The set-up consists of securing the sensor on the calibration mount and checking the side-slip angle (β) of the plate so the flow becomes just attached.

Channels 12 and 13 of the DAS are then zeroed. This is done using the 5K Ω potentiometer of Figure 2.4. In effect, this is causing the output of the fore and aft thermistors to equal, negatively. Once initialized, the calibration process can begin.

4.4 PROCEDURES

The calibration procedures follow the computer listing of Appendix B on Page 81. Once initialized, the computer asks for the tunnel dynamic pressure, which is the differential pressure of the sensor. As the desired tunnel dynamic pressure is attained, the DAS takes 10 sampled values and obtains the average. This average is then used in the output and for plotting purposes. Table 4.1 gives the output of a typical calibration run. The output is then plotted in Figure 4.6. As indicated in the output, the tunnel dynamic pressure range is from 0 to 35 cm of alcohol, or 0 to 27.2 psf.



TUNNEL MANOMETER READING, T-cm ALCOHOL

| | | | | |
|-------|-------------------|------|---------|------|
| CALC | <i>David King</i> | 8/18 | REVISED | DATE |
| CHECK | | | | |
| APPO | | | | |
| APPO | | | | |

Figure 4.6 Sensor Calibration Curve

Table 4.1 Calibration Run Data

| Manometer Dynamic Pressure (cm. of alcohol) | Transducer Output (mVolts) |
|--|-------------------------------|
| 0 | - 0.060 |
| 2.5 | - 0.982 |
| 5.0 | - 1.185 |
| 7.5 | - 1.183 |
| 10.0 | - 1.290 |
| 12.5 | - 1.464 |
| 15.0 | - 1.538 |
| 17.5 | - 1.525 |
| 20.0 | - 1.410 |
| 22.5 | - 1.225 |
| 25.0 | - 1.140 |
| 27.5 | - 1.083 |
| 30.0 | - 1.049 |
| 32.5 | - 0.982 |
| 35.0 | - 0.889 |

4.5 RESULTS AND DISCUSSION

The results of the calibration tests indicate that for this type of application, the sensor is not adequate due to shortcomings in two areas:

- 1) Sensor range
- 2) Dynamic response.

It was found that the sensor produced a linear output only up to approximately 2 psf. In addition, the sensor became completely saturated at values up to 13 psf. As outlined in Section 3.6, the required linear range of the sensor is ± 30 psf.

A pressure sensor can usually be mathematically modelled by a pure lag. Although specific dynamic response tests were not performed, it was observed that approximately 10 seconds was

required for the sensor output to return to zero after a pressure differential was removed. This type of response is unacceptable in a feedback control system.

4.6 MODIFICATIONS AND SUBSEQUENT RESULTS

Various methods were tried to obtain different sensor characteristics. The following methods were suggested by Jim Black, designer of the sensor:

- 1) Change sensor port diameter
- 2) Change amplifier gain.

4.6.1 SENSOR PORT DIAMETER

The sensor port diameter was changed from the original diameter of .025" to a diameter of .0135". This was done by plugging both ports on the calibration mount with epoxy. The epoxy was then drilled out to a .0135" diameter (#80 drill).

The calibration process was then repeated. It was found that while the sensor range was slightly increased, the dynamic response characteristics were degraded.

4.6.2 AMPLIFIER GAIN

The amplifier (sensor) was altered by changing the resistance of the input resistor to the amplifier of Figure 2.4. The amplifier gain was changed to values of .01, .10, and .50. Again, the saturation point remained unchanged.

4.6.3 AMPLIFIER VOLTAGE

The sensor circuit of Figure 2.4 defines the input voltage to the amplifier as +22 volts d.c. The amplifier voltage used in the testing was set at 15 volts d.c. To see if any difference would result, the voltage was increased to 18 volts d.c. (the limit voltage for the LM 324N OP AMP). This tended to increase the saturation point, but still not to the required value. The linear range appeared to be unchanged.

4.6.4 MIDDLE THERMISTOR

A sensor thermistor profile was conducted to determine how the voltage, current, and resistance of each thermistor in the sensor was changing as the pressure differential increased. It was concluded that the middle thermistor was not able to increase its power output after a relatively low pressure was applied to the sensor. Four (4) different thermistors replaced the middle thermistor to check this theory. Using values of 5K, 10K, 50K, and 100K Ω , the power output of the middle thermistor was increased. The results were encouraging but still saturated out before maximum estimated pressure differential occurred.

4.7 CONCLUSIONS AND RECOMMENDATIONS

The sensor is not suitable for the purpose of this study. There are two types of pressure sensors available today that meet the needs of the project.

Conventional diaphragm pressure sensors have the range, accuracy, and dynamic response required but are relatively expensive.

A Piezoresistive sensor offers the same qualities for a reasonable cost. A brief literature search is recommended before final selection is made.

5. PHASE III: FREQUENCY RESPONSE

Phase III of this study is designed to determine the transfer function for the system, actuator, and sensor. The circuit can be either assumed to be a pure gain, or determined analytically. Once these transfer functions are known, a closed loop analysis of a typical feedback control system can be performed, and the stability determined. A theoretical analysis of a typical control system is included in Section 6.2.

Phase III is composed of Parts A, B, and C. The objective of Part A is to obtain standard lift, drag, and pitching moment coefficients and their variations with α and δ_F . The run schedule for Part A is given in Table 5.1.

Table 5.1 Part A Run Schedule



| Run No. | α | δ_F (degrees) | q (psf) |
|---------|----------|----------------------|---------|
| 1 | ① ↓ | - 20 | 25 ↓ |
| 2 | | - 15 | |
| 3 | | - 10 | |
| 4 | | - 5 | |
| 5 | | 0 | |
| 6 | | + 5 | |
| 7 | | + 10 | |
| 8 | | + 15 | |
| 9 | | + 20 | |

Note: ① $\alpha = -8, -6, -4, -2, 0, +2, +4, +6, +8$ (degrees)

Part B of Phase III is designed to obtain preliminary data on system performance at various angles of attack and initial flap positions. (Several of the runs may be deleted if the initial

indications are promising.) This is accomplished by applying a step input to the pressure sensor via the signal conditioner control box. The run schedule for Part B is given in Table 5.2.

Table 5.2 Part B Run Schedule

| Run No. | α (deg) | $\Delta P_{\text{COMMAND}}^*$ | $\delta_{F_{\text{INITIAL}}}$ (deg) | q (psf) |
|---------|----------------|---|-------------------------------------|--|
| 1 | - 8 | <div style="text-align: center;"> 2  </div> | - 10 | <div style="text-align: center;"> 25  </div> |
| 2 | - 8 | | 0 | |
| 3 | - 4 | | - 10 | |
| 4 | - 4 | | 0 | |
| 5 | 0 | | - 10 | |
| 6 | 0 | | 0 | |
| 7 | + 4 | | - 10 | |
| 8 | + 4 | | 0 | |
| 9 | + 8 | | - 10 | |
| 10 | + 8 | | 0 | |

Note: ② $\Delta C_p = 0.1, 0.3, 0.5, 1.0$ or
 $\Delta P = 2.5, 7.5, 12.5, 25$ psf at $q = 25$ psf

The data obtained will be presented as illustrated in Figure 5.1.




Figure 5.1 Response to a Step Input

Part C will be used to determine the necessary frequency response characteristics of the system. A total of 18 windtunnel runs will be used to obtain the data, each containing the following:

| INPUTS | OUTPUTS |
|--|--|
| $\delta_{F\text{ IN}}(t) = \delta_{F\text{ IN}} \cos \omega t$ | $\delta_{F\text{ OUT}}(t) = \delta_{F\text{ OUT}} \cos(\omega t + \phi_1)$ |
| | $\Delta P_{\text{OUT}}(t) = \Delta P_{\text{OUT}} \cos(\omega t + \phi_2)$ |
| $\Delta P_{\text{IN}}(t) = \Delta P_{\text{IN}} \cos \omega t$ | $\delta_{F\text{ OUT}}(t) = \delta_{F\text{ OUT}} \cos(\omega t + \phi_3)$ |
| | $\Delta P_{\text{OUT}}(t) = \Delta P_{\text{OUT}} \cos(\omega t + \phi_4)$ |

The reader should note the following:

- 1) δ_F inputs directly into the actuator.
- 2) ΔP inputs into the control circuit.
- 3) Frequency range: $.01 < \omega < 1000$ rad/sec.

Tables 5.3 (a) and (b) give the run schedules for this part of the frequency response testing. The sinusoidal inputs to the actuator and sensor will be accomplished by connecting a function generator to the appropriate inputs on the signal conditioner. A two-channel strip chart recorder will be used to monitor the outputs of the sensor and L.V.D.T.

The data obtained during this phase of the study would be presented in the form of a standard bode plot. It will be from these plots that a transfer function will be derived. These transfer functions will then be tested against those used in the theoretical analysis of Section 6.2.

Table 5.3(a) Frequency Response Test Runs - Position

| Run No. | α (deg) | $ \delta_{F_{IN}} $ | $ \Delta P_{IN} $ | q (psf) |
|---------|------------------|---------------------|-------------------|---------|
| 1 | - 8 ^o | ③ | - | 25 |
| 2 | - 6 | ↓ | - | ↓ |
| 3 | - 4 | ↓ | - | ↓ |
| 4 | - 2 | ↓ | - | ↓ |
| 5 | 0 | ↓ | - | ↓ |
| 6 | + 2 | ↓ | - | ↓ |
| 7 | + 4 | ↓ | - | ↓ |
| 8 | + 6 | ↓ | - | ↓ |
| 9 | + 8 | ↓ | - | ↓ |

Table 5.3(b) Frequency Response Test Runs - Pressure

| Run No. | α (deg) | $ \delta_{F_{IN}} $ | $ \Delta P_{IN} $ | q (psf) |
|---------|----------------|---------------------|-------------------|---------|
| 1 | - 8 | - | ② | 25 |
| 2 | - 6 | - | ↓ | ↓ |
| 3 | - 4 | - | ↓ | ↓ |
| 4 | - 2 | - | ↓ | ↓ |
| 5 | 0 | - | ↓ | ↓ |
| 6 | + 2 | - | ↓ | ↓ |
| 7 | + 4 | - | ↓ | ↓ |
| 8 | + 6 | - | ↓ | ↓ |
| 9 | + 8 | - | ↓ | ↓ |

Note: ② $|\Delta P_{IN}|$ = 2.5, 7.5, 12.5, 25 psf at q = 25 psf

③ $|\delta_{F_{IN}}|$ = 5, 10, 15, 20 degrees

6. THEORETICAL ANALYSIS


6.1 THEORETICAL PRESSURE DISTRIBUTION

The windtunnel test described in Chapter 3 required significant amounts of time, manpower, and hardware development. It is desirable to find a way to bypass the need for this test. If a commonly used airfoil with the necessary testing already performed (e.g., NACA 4 and 5 digit airfoils) is chosen, then the published results can be used instead of repeating the test. However, the test surface employed for this study incorporated a unique airfoil (see Figure 6.1) with an unknown pressure distribution. Therefore, to avoid windtunnel testing, numerical methods must be used. The method used for this study was the NASA/Langley Single Element Airfoil Program (SEAP), which was stored on the University of Kansas Honeywell 66/60.

The program requires, as input, the airfoil coordinates listed in Table 6.1. Mach number and Reynolds number inputs are the same as in the Phase I testing. Included in the output is a listing of the pressure coefficients at chordwise stations along the airfoil (see Appendix B for sample output).

A total of 16 cases were input to the program—four angles of attack ($\alpha = 0, 3, 6, 9^\circ$) and four flap deflections ($\delta_F = 0, 5, 10, 15^\circ$). It is assumed that symmetry holds with respect to angle of attack and flap deflections. Flap deflections are input to the program by altering the airfoil coordinates aft of the hingeline (see Figure 6.2 and Table 6.2). Due to difficulties with software, results were not obtained for the case of $\alpha = 9^\circ$, $\delta_F = 0^\circ$.

| AIRFOIL SPECIFICATIONS | |
|------------------------|----------------|
| $(c/c)_{MAX}$ | = .20 |
| $x_{c/c_{MAX}}$ | = .135c |
| L.E.R. | = .08c |
| Δy | = .148c |
| $\phi_{T.E.}$ | = 12.5° |
| e/c | = .306 |




| | | | |
|-------|--------|---------|------|
| DATE | 6/1/81 | REVISED | DATE |
| CHIEF | | | |
| APPO | | | |
| APPO | | | |

Figure 6.1 Delta P Airfoil Section

UNIVERSITY OF KANSAS

PAGE 38



| | | | | |
|-------|---------|-----|---------|------|
| CALC | D. LEVY | 5/6 | REVISED | DATE |
| CHECK | | | | |
| APPD | | | | |
| APPD | | | | |

Figure 6.2 Airfoil with Flap Deflections

Table 6.1 Delta P Airfoil Coordinates - Zero Flap Deflection

| XU (=XL) | ZU (= -ZL) | XU (=XL) | ZU (= -ZL) |
|----------|------------|----------|------------|
| 0 | 0 | .325 | .080 |
| .00625 | .032 | .350 | .077 |
| .0125 | .043 | .375 | .074 |
| .01875 | .052 | .400 | .071 |
| .0250 | .057 | .425 | .06825 |
| | | | |
| .03125 | .064 | .450 | .0655 |
| .0375 | .069 | .475 | .06275 |
| .04375 | .073 | .500 | .060 |
| .0500 | .077 | .525 | .05725 |
| .05625 | .081 | .550 | .0545 |
| | | | |
| .0625 | .083 | .575 | .05175 |
| .06875 | .085 | .600 | .049 |
| .0750 | .087 | .625 | .04625 |
| .08125 | .090 | .650 | .0435 |
| .0875 | .092 | .675 | .04075 |
| | | | |
| .09375 | .093 | .700 | .038 |
| .100 | .094 | .725 | .035 |
| .1125 | .0965 | .750 | .032 |
| .125 | .098 | .775 | .029 |
| .1375 | .100 | .800 | .026 |
| | | | |
| .150 | .099 | .825 | .02325 |
| .1625 | .0985 | .858 | .0205 |
| .175 | .097 | .875 | .01775 |
| .1875 | .096 | .900 | .015 |
| .200 | .095 | .925 | .01225 |
| | | | |
| .225 | .092 | .950 | .0095 |
| .250 | .089 | .975 | .00675 |
| .275 | .086 | 1.000 | .004 |
| .300 | .083 | | |

Table 6.2 Delta P Airfoil Coordinates - Flap Deflection = 5, 10, 15 (degrees)

Substitute into Table 6.1 for $.70 \leq XU \leq 1.00$

| XU (=XL) | $\delta_F = 5^\circ$ | | $\delta_F = 10^\circ$ | | $\delta_F = 15^\circ$ * | |
|----------|----------------------|--------|-----------------------|--------|-------------------------|-------|
| | ZU | ZL | ZU | ZL | ZU | ZL |
| .700 | .038 | -.040 | .038 | -.041 | .037 | -.043 |
| .725 | .032 | -.039 | .0305 | -.0425 | - | - |
| .750 | .027 | -.038 | .023 | -.044 | .017 | -.050 |
| .775 | .022 | -.037 | .0155 | -.0455 | - | - |
| .800 | .017 | -.036 | .009 | -.047 | -.003 | -.057 |
| | | | | | | |
| .825 | .012 | -.0355 | .0005 | -.0485 | - | - |
| .850 | .007 | -.035 | -.007 | -.050 | -.023 | -.064 |
| .875 | .002 | -.034 | -.0145 | -.051 | - | - |
| .900 | -.003 | -.033 | -.022 | -.052 | -.043 | -.071 |
| .925 | -.008 | -.032 | -.0295 | -.0535 | - | - |
| | | | | | | |
| .950 | -.013 | -.031 | -.037 | -.055 | -.063 | -.078 |
| .975 | -.018 | -.030 | -.0445 | -.0565 | - | - |
| 1.000 | -.023 | -.029 | -.052 | -.058 | -.083 | -.083 |

* For the $\delta_F = 15^\circ$ case, it was necessary to input a slightly fewer number of coordinates. Since the aft portion of the surface is essentially flat, this is considered to make little, if any, difference.

The C_p values generated are at distributed points (chosen by the computer) along the airfoil. Consequently, for comparison with the windtunnel data, the pressure coefficients are interpolated to the 13 chordwise locations of the test surface. Then the same data reduction process outlined in Subsection 3.5.2 is performed on the data. The results are tabulated and plotted in Appendix C.

From Figures C.1 through C.26 it is seen that the general sensitivity trends follow those of the windtunnel data. However, contrary to the experimental data, the pressure differential, at all locations, is sensitive to flap deflection. In addition, the results are somewhat nonlinear--especially at the five degree flap deflection case. The maximum C_p predicted by the SEAP at $x/c = .766$ agrees reasonably well with the experimental data, but this is not the case at the forward tap locations.

There are a few explanations for the discrepancies between the experimental and theoretical data. First, the large thickness ratio (t/c) and extreme forward location of the maximum t/c might not lend itself to accurate analysis by the SEAP. Second, since the program is not specifically designed to handle flap deflections, the method of doing so could lead to errors. Finally, the program utilizes a two-dimensional analysis technique, while the windtunnel test is three dimensional.

While the results of the theoretical analysis do not correlate exactly with the experimental data, they are promising enough to prompt further study. Analysis of other airfoils, perhaps with another computer program more suited to the specific needs of the project, is recommended before discounting the theoretical approach.

6.2 CLOSED LOOP DYNAMIC STABILITY ANALYSIS

A study has been performed to see what the closed loop performance of a system is (or should be) that incorporates differential pressure command as opposed to elevator position command. In analyzing the system, the block diagram of Figure 6.3 is used. The system illustrated is a pitch attitude hold loop which uses pressure as the feedback quantity in the δ_E inner loop. As a control a conventional pitch attitude hold system which incorporates elevator position command (of Figure 6.4) was also analyzed.

For simplification, the amplifier of the inner loop has been assumed to be a pure gain, equal to unity:

$$K_{AMP} = 1 \quad (6.1)$$

The elevator servo is assumed to be a first order lag:

$$\frac{\delta_E(s)}{\delta_{EOUT}(s)} = \frac{10}{s + 10} \quad (6.2)$$

The break frequency of 10 rad/sec is representative of a reasonably fast, general aviation actuator.

The sensor calibration constant, or position command gain, is a function of dynamic pressure and is obtained from the numerical regression of Chapter 10, Part II, of this report:

$$\frac{\partial \Delta C_P}{\partial \delta_F} = .047 \quad (6.3)$$

or:

$$\frac{\partial \Delta P}{\partial \delta_F} = K_{SENSOR \& CIRCUIT} = .047q \quad (6.4)$$




Figure 6.3 System Block Diagram (Pressure Command)




Figure 6.4 System Block Diagram (Position Command)

The aerodynamic lag^{*} and the sensor lag are combined into one first order transfer function:

$$\frac{\delta_{E_{IN}}(s)}{\Delta P_{OUT}(s)} = \frac{a}{s+a} = \frac{5}{s+5} \quad (6.5)$$

The break frequency of 5 rad/sec has been assumed as "reasonable."

The experimental determination of this lag is one of the major purposes of the Phase III windtunnel test.

The airplane $\frac{\theta(s)}{\delta_E(s)}$ transfer function is derived using data obtained from Appendix B of Reference 4 for a typical general aviation airplane. To investigate the effect of dynamic pressure on system performance, high and low values were used:

Case 1: $q = 8.47$ psf ($K_g = .40$)


Case 2: $q = 76.28$ psf ($K_g = 3.59$)

Using Reference 5 in conjunction with the University of Kansas Aerospace Engineering Department's HP9825A micro-minicomputer, the airplane $\frac{\theta(s)}{\delta_E(s)}$ transfer function was derived for each case; and the root loci of Figures 6.5 through 6.8 were generated. The computer output used to construct the root loci is located in Appendix D. Notice that with the inner loop pressure command, the sensor and actuator combine to form an oscillatory pair. In fact, Figure 6.6 shows that it is these poles which go unstable at high dynamic pressure.


It can be seen from the figures that a loop gain equal to

$$K_\theta = 1.0 \quad (6.6)$$

* The aerodynamic lag represents the lag between a change in δ_E and the resulting pressure change at the sensor.




| | | | | | | |
|----------------------|--------------|--|---------|--------|--|---------|
| CALC | R. L. HARRIS | | REVISED | DATE | Figure 6.5 Pitch Attitude Hold for Airplane A (App. C, Ref 4) with Pressure Sensor (q= 8.5 psf) | PAGE 45 |
| CHECK | | | | 9/5/61 | | |
| APPD | | | | | | |
| APPD | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | |



| | | | | |
|-------|-----------|--|---------|------|
| CALC | R. HAAGAN | | REVISED | DATE |
| CHECK | | | 6/6/61 | |
| APPO | | | | |
| APPO | | | | |

Figure 6.6 Pitch Attitude Hold for Airplane A (App. C, Ref 4) with Pressure Sensor ($q = 76.3$ psf)



| | | | | | | |
|-------|-----------|--|---------|--------|--|---------|
| CALC | R. HODGAK | | REVISED | DATE | Figure 6.7 Pitch Attitude Hold for Airplane A (App. C, Ref 4) (q= 8.5 psf) | |
| CHECK | | | | 8/5/81 | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 47 |

yields reasonable damping ratios and natural frequencies for the pressure sensor pitch attitude hold system. It is also observed that in the system with the pressure sensor, the gain margin remains relatively constant with dynamic pressure as compared to the conventional system. It appears that gain scheduling with dynamic pressure can be avoided without a compensator or inner loop pitch damping.

Again it should be noted that the sensor properties have not been determined. The frequency response data obtained during Phase III will yield the necessary information for a more detailed study. This analysis is merely a preliminary investigation of the closed loop characteristics of the pressure feedback system.

7. CONCLUSIONS AND RECOMMENDATIONS

The sensor used in this study does not have the qualities required to determine the feasibility of differential pressure feedback in a flight control system. Of available sensors, the piezoresistive has the characteristics most suited for this type of application.

Once this concept has been proven feasible, a follow-up program is recommended which will include the use of a more conventional airfoil. Within this program, both theoretical and experimental pressure distributions should be investigated.

PRECEDING PAGE BLANK NOT FILMED

8. REFERENCES

1. Proposal for a Program to Evaluate a Control System Based on Feedback of Aerodynamic Pressure Differentials; Submitted to NASA Dryden Flight Research Center, July 1980; University of Kansas Center for Research, Inc., Flight Research Lab.
2. Daugherty, D. G.; A Critical Review of an Automatic Attitude Command Control System Electronics Design; Flight Research Laboratory Report FRL 325, The University of Kansas, Lawrence, Kansas, November 1974.
3. Pope, A.: Low-speed Wind Tunnel Testing; John Wiley and Sons, 1966.
4. Roskam, J.; Airplane Flight Dynamics and Automatic Flight Controls, Part II; Published by the Author, Ottawa, Kansas, 1979.
5. Clarke, Robert; A Computer Program for Determining Open and Closed Loop Dynamics of Airplanes; The University of Kansas, Lawrence, Kansas, May 1980.

PRECEDING PAGE BLANK NOT FILMED


APPENDIX A
PRESSURE PROFILE SENSITIVITY PLOTS

PRECEDING PAGE BLANK NOT FILMED

A.1 FLAP DEFLECTION

PRECEDING PAGE BLANK NOT FILMED


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE 13
OF POOR QUALITY


| | | | | | | |
|-------|---------|---------|---------|------|--|---------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.1 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE |
| CHECK | D. LEVY | 5/13/61 | | | | 20-5-81 |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 58 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.2 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY UNIVERSITY OF KANSAS | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPRO | | | | | | |
| APPRO | | | | | | PAGE 39 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | |
|-------|---------|---------|---------|------|
| CALC | P. FINN | 5-01 | REVISED | DATE |
| CHECK | D. LEVY | 5/25/61 | | |
| APPRO | | | | |
| APPRO | | | | |


FIGURE A.1.3 EXPERIMENTAL CHANGE IN
PRESSURE COEFFICIENTS
- FLAP DEFLECTION
SENSITIVITY

UNIVERSITY OF KANSAS

DATE
20-5-01


PAGE
60

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.4 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- FLAP DEFLECTION</u> <u>SENSITIVITY</u> | DATE 20-5-81 |
| CHECK | D. LEVY | 5/75/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 61 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.5 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 64 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|-------|---------|---------|---------|------|--|---------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.6 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- FLAP DEFLECTION</u> <u>SENSITIVITY</u> | DATE |
| CHECK | D. LEVY | 5/25/81 | | | | 20-5-81 |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 63 |


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.7 EXPERIMENTAL CHANGE IN <u>PRESSURE COEFFICIENTS</u> <u>- FLAP DEFLECTION</u> <u>SENSITIVITY</u> | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 64 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|----------------------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.1.8 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- FLAP DEFLECTION</u> <u>SENSITIVITY</u> | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPRO | | | | | | |
| APPRO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 65 |


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY

| | | | | | | |
|----------------------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 1.9 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 66 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFAC TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 1. 10 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY UNIVERSITY OF KANSAS | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | PAGE 67 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 1. 11 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/84 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 68 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 1. 12 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 69 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




FINAL PAGE IS
OF POOR QUALITY

| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 1. 13 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- FLAP DEFLECTION</u> <u>SENSITIVITY</u> | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 70 |

A.2 ANGLE OF ATTACK


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|----------------------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.1 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 28-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 72 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.2 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPRO | | | | | | |
| APPRO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 73 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 2.3 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 74 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|--------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.4 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 20-5-81 |
| CHECK | D. LEVY | 5/2/81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 75 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.5 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- /NGLE OF ATTACK</u> <u>SENSITIVITY</u> | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 76 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | |
|-------|---------|---------|---------|------|
| CALC | P. FINN | 5-81 | REVISED | DATE |
| CHECK | D. LEVY | 5/25/81 | | |
| APPO | | | | |
| APPO | | | | |


FIGURE A.2.6 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY

UNIVERSITY OF KANSAS

DATE
20-5-81


PAGE
77

NOTE: LOYER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|----------------------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 3-61 | REVISED | DATE | FIGURE A.2.7 <u>EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS</u> <u>- ANGLE OF ATTACK SENSITIVITY</u> | DATE 20-5-81 |
| CHECK | D. LEVY | 5/27/51 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 78 |


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.8 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 20-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 79 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|--|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.9 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - <u>ANGLE OF ATTACK</u> <u>SENSITIVITY</u> | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 80 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION




| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.10 <u>EXPERIMENTAL CHANGE IN</u> <u>PRESSURE COEFFICIENTS</u> <u>- ANGLE OF ATTACK</u> <u>SENSITIVITY</u> | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 81 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A. 2. 11 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY UNIVERSITY OF KANSAS | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | PAGE 82 |


NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY

| | | | | | | |
|-------|---------|---------|---------|------|---|-----------------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.12 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 21-5-81 |
| CHECK | D. LEVY | 5/25/81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 83 |

NOTE: LOWER SURFACE C_p INTERPOLATED TO UPPER SURFACE TAP LOCATION



ORIGINAL PAGE IS
OF POOR QUALITY

| | | | | | | |
|-------|---------|---------|---------|------|---|---------|
| CALC | P. FINN | 5-81 | REVISED | DATE | FIGURE A.2.13 EXPERIMENTAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE |
| CHECK | D. LEVY | 5/25/81 | | | | 21-5-81 |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 84 |

APPENDIX B. PRESSURE TRANSDUCER CALIBRATION PROGRAM

```

240: wrt 4
241: wrt 4,"          DELTA P PRESSURE TRANSDUCER CALIBRATION"
242: wrt 4
243: wrt 4," THE PRESSURE TRANSDUCER WILL BE CALIBRATED AGAINST THE TUNNEL"
244: wrt 4," MANOMETER BOARD LOCATED ON THE NORTH SIDE OF THE TUNNEL BELL"
245: wrt 4," THE TRANSDUCER MUST BE HOOKED TO CHANNEL 12 OF THE DAS"
246: wrt 4
247: wrt 4
248: wrt 4,"PROCEDURE:"
249: wrt 4
250: wrt 4," TO CALIBRATE, THE TUNNEL WILL BE RUN AT VARIOUS ASSIGNED SPEEDS."
251: wrt 4," THE hp 9825 WILL RECORD THE PRESSURE TRANSDUCER OUTPUT AND "
252: wrt 4," THE OPERATOR WILL ADJUST THE TUNNEL SPEED TO THE MANOMETER VALUE"
253: wrt 4," REQUESTED BY THE CALCULATOR DISPLAY"
254: wrt 4:wr 4
255: ent "DATE  TRANSDUCER NUMBER",D$
256: utb 5,12+6
257: wrt 6:wr 6:wr 6:wr 6:wr 6,"          PRESSURE TRANSDUCER CALIBRATION ",D$
258: wrt 6,"          ",G$
259: wrt 6,"          MANOMETER Q          TRANSDUCER OUTPUT"
260: csiz 2,2,1,0
261: ent "DO YOU WISH A GRAPH ? Y or N",A$
262: if cap(A$)="Y"fcisz 2,2,1,0
263: if cap(A$)="Y"fxd 0:sc1 0,35,0,2:rox 0,5,0,2:ax 0,5,0,35,1
264: if cap(A$)="Y"fp1t 3,-.5,-1fcisz 2,2,1,0
265: if cap(A$)="Y"fb1 " TUNNEL DYNAMIC PRESSURE - Q (cm H2O)"
266: if cap(A$)="Y"fp1t -5,.5,-1fcisz 2,2,1,0
267: if cap(A$)="Y"fb1 " TRANSDUCER OUTPUT - Q1 (mV)"
268: if cap(A$)="Y"fcisz 2,5,2,1,0fp1t 5,-.8,-1
269: if cap(A$)="Y"fb1 " PRESSURE TRANSDUCER CALIBRATION ",D$
270: if cap(A$)="Y"fp1t 2,5,2,4,-1fcisz 2,2,1,0
271: fb1 "Q = (TUNNEL MANOMETER * SIN30)"
272: for Q=0 to 35 by 5
273: fxd 0:0-S
274: dsp "TUNNEL Q (cmH2O)",Q,"CONT W. RDY"fb1
275: for I=1 to 50
276: red 3,A,B
277: if B>15-A-A
278: A+S+S
279: next I
280: fnt 4,2x,f4,0,20x,f10,3
281: wrt 6,4,0,20S
282: if cap(A$)="Y"fp1t Q,-20Sfp1t -.165,-.05fb1 "*"
283: next Q

```

APPENDIX C

THEORETICAL PRESSURE PROFILE DATA

PRECEDING PAGE BLANK NOT FILMED

C.1 SAMPLE LISTING OF SEAP OUTPUT

PRECEDING PAGE BLANK NOT FILMED

MODEL A P THEORETICAL PRESSURE DISTRIBUTION

DRAG COEFFICIENT COMPUTED BY SOWIRE-YOUDS FORMULA = 0.01599

ITERATION PRESSURE DRAG = -0.01341

U/C (UPPER) = 0.00127

LONGEST CHORD IN A SYSTEM

BASIC REFERENCE SYSTEM

[illegible]

PRECEDING PAGE BLANK NOT FILMED

C.2 PRESSURE DISTRIBUTION DATA

AS INPUT TO HP9825 A

PRECEDING PAGE BLANK NOT FILMED

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0
FILE NUMBER 34

FLAP DEFLECTION ANGLE = 0

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.060 | -1.198 | -1.198 |
| 2 | * | 0.076 | -1.135 | -1.135 |
| 3 | * | 0.084 | -1.396 | -1.396 |
| 4 | * | 0.094 | -1.354 | -1.354 |
| 5 | * | 0.108 | -1.216 | -1.216 |
| 6 | * | 0.121 | -1.277 | -1.277 |
| 7 | * | 0.133 | -1.450 | -1.450 |
| 8 | * | 0.143 | -1.365 | -1.365 |
| 9 | * | 0.155 | -1.081 | -1.081 |
| 10 | * | 0.169 | -0.881 | -0.881 |
| 11 | * | 0.184 | -0.743 | -0.743 |
| 12 | * | 0.205 | -0.648 | -0.648 |
| 13 | * | 0.228 | -0.572 | -0.572 |
| 14 | * | 0.250 | -0.334 | -0.334 |
| 15 | * | 0.381 | -0.264 | -0.264 |
| 16 | * | 0.416 | -0.136 | -0.136 |
| 17 | * | 0.480 | -0.115 | -0.115 |
| 18 | * | 0.680 | -0.103 | -0.103 |
| 19 | * | 0.715 | -0.076 | -0.076 |
| 20 | * | 0.750 | -0.070 | -0.070 |
| 21 | * | 0.785 | -0.042 | -0.042 |
| 22 | * | 0.820 | -0.029 | -0.029 |
| 23 | * | 1.000 | 0.634 | 0.634 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 35

FLAP DEFLECTION ANGLE = 0

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.060 | -1.860 | -0.612 |
| 2 | * | 0.076 | -1.728 | -0.603 |
| 3 | * | 0.084 | -1.989 | -0.849 |
| 4 | * | 0.094 | -1.877 | -0.854 |
| 5 | * | 0.108 | -1.665 | -0.777 |
| 6 | * | 0.121 | -1.702 | -0.855 |
| 7 | * | 0.133 | -1.887 | -1.019 |
| 8 | * | 0.143 | -1.786 | -0.965 |
| 9 | * | 0.155 | -1.445 | -0.744 |
| 10 | * | 0.169 | -1.192 | -0.591 |
| 11 | * | 0.184 | -1.009 | -0.490 |
| 12 | * | 0.205 | -0.881 | -0.423 |
| 13 | * | 0.228 | -0.788 | -0.364 |
| 14 | * | 0.250 | -0.476 | -0.193 |
| 15 | * | 0.381 | -0.381 | -0.145 |
| 16 | * | 0.416 | -0.209 | -0.057 |
| 17 | * | 0.480 | -0.177 | -0.050 |
| 18 | * | 0.680 | -0.159 | -0.045 |
| 19 | * | 0.715 | -0.119 | -0.035 |
| 20 | * | 0.750 | -0.115 | -0.028 |
| 21 | * | 0.785 | -0.080 | -0.006 |
| 22 | * | 0.820 | -0.063 | -0.002 |
| 23 | * | 1.000 | 0.630 | 0.630 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6
FILE NUMBER 36

FLAP DEFLECTION ANGLE = 0

RESULTS OF SEAP DATA

| TAP NUMBER | * * | x/c location | Cp upper | Cp lower |
|---------------|--------|-----------------|-------------|-------------|
| 1 | * | 0.060 | -2.624 | -0.093 |
| 2 | * | 0.076 | -2.407 | -0.124 |
| 3 | * | 0.084 | -2.670 | -0.345 |
| 4 | * | 0.094 | -2.489 | -0.382 |
| 5 | * | 0.108 | -2.190 | -0.355 |
| 6 | * | 0.121 | -2.194 | -0.444 |
| 7 | * | 0.133 | -2.383 | -0.598 |
| 8 | * | 0.143 | -2.240 | -0.578 |
| 9 | * | 0.155 | -1.822 | -0.418 |
| 10 | * | 0.169 | -1.512 | -0.308 |
| 11 | * | 0.184 | -1.283 | -0.240 |
| 12 | * | 0.205 | -1.121 | -0.198 |
| 13 | * | 0.228 | -1.008 | -0.156 |
| 14 | * | 0.250 | -0.626 | -0.047 |
| 15 | * | 0.381 | -0.510 | -0.018 |
| 16 | * | 0.416 | -0.298 | 0.033 |
| 17 | * | 0.480 | -0.248 | 0.026 |
| 18 | * | 0.680 | -0.221 | 0.022 |
| 19 | * | 0.715 | -0.163 | 0.016 |
| 20 | * | 0.750 | -0.162 | 0.024 |
| 21 | * | 0.785 | -0.119 | 0.039 |
| 22 | * | 0.820 | -0.096 | 0.036 |
| 23 | * | 1.000 | 0.624 | 0.624 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0

FLAP DEFLECTION ANGLE = 5

FILE NUMBER 37

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.062 | -1.340 | -1.022 |
| 2 | * | 0.073 | -1.285 | -0.949 |
| 3 | * | 0.083 | -1.572 | -1.148 |
| 4 | * | 0.094 | -1.501 | -1.202 |
| 5 | * | 0.107 | -1.359 | -1.063 |
| 6 | * | 0.123 | -1.486 | -1.116 |
| 7 | * | 0.135 | -1.627 | -1.266 |
| 8 | * | 0.148 | -1.324 | -1.146 |
| 9 | * | 0.163 | -1.032 | -0.886 |
| 10 | * | 0.181 | -0.903 | -0.714 |
| 11 | * | 0.293 | -0.596 | -0.436 |
| 12 | * | 0.296 | -0.418 | -0.275 |
| 13 | * | 0.404 | -0.214 | -0.076 |
| 14 | * | 0.652 | -0.158 | -0.008 |
| 15 | * | 0.671 | -0.027 | 0.215 |
| 16 | * | 0.688 | -0.060 | 0.157 |
| 17 | * | 0.704 | -0.039 | 0.144 |
| 18 | * | 0.720 | 0.020 | 0.124 |
| 19 | * | 0.741 | -0.022 | 0.068 |
| 20 | * | 0.795 | -0.067 | 0.033 |
| 21 | * | 0.824 | -0.043 | 0.008 |
| 22 | * | 0.852 | -0.102 | -0.088 |
| 23 | * | 1.000 | 0.760 | 0.760 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 38

FLAP DEFLECTION ANGLE = 5

RESULTS OF SERP DATA

| TAP NUMBER | * * | x/c location | Cp upper | Cp lower |
|---------------|--------|-----------------|-------------|-------------|
| 1 | * | 0.062 | -1.607 | -0.748 |
| 2 | * | 0.073 | -1.513 | -0.712 |
| 3 | * | 0.083 | -1.803 | -0.912 |
| 4 | * | 0.094 | -1.703 | -0.984 |
| 5 | * | 0.107 | -1.524 | -0.881 |
| | * | | | |
| 6 | * | 0.123 | -1.632 | -0.951 |
| 7 | * | 0.135 | -1.767 | -1.107 |
| 8 | * | 0.148 | -1.452 | -1.006 |
| 9 | * | 0.163 | -1.141 | -0.773 |
| 10 | * | 0.181 | -1.001 | -0.619 |
| | * | | | |
| 11 | * | 0.203 | -0.644 | -0.384 |
| 12 | * | 0.296 | -0.438 | -0.250 |
| 13 | * | 0.404 | -0.178 | -0.105 |
| 14 | * | 0.652 | -0.097 | -0.060 |
| 15 | * | 0.671 | 0.122 | 0.078 |
| | * | | | |
| 16 | * | 0.688 | 0.091 | 0.009 |
| 17 | * | 0.704 | 0.123 | -0.020 |
| 18 | * | 0.720 | 0.158 | -0.022 |
| 19 | * | 0.741 | 0.080 | -0.039 |
| 20 | * | 0.795 | 0.017 | -0.053 |
| | * | | | |
| 21 | * | 0.824 | 0.039 | -0.077 |
| 22 | * | 0.852 | -0.024 | -0.174 |
| 23 | * | 1.000 | 0.750 | 0.750 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 5
 FILE NUMBER 39

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.062 | -1.905 | -0.469 |
| 2 | * | 0.073 | -1.773 | -0.464 |
| 3 | * | 0.083 | -2.063 | -0.661 |
| 4 | * | 0.094 | -1.925 | -0.748 |
| 5 | * | 0.107 | -1.707 | -0.680 |
| 6 | * | 0.123 | -1.798 | -0.764 |
| 7 | * | 0.135 | -1.914 | -0.932 |
| 8 | * | 0.148 | -1.563 | -0.860 |
| 9 | * | 0.163 | -1.230 | -0.652 |
| 10 | * | 0.181 | -1.083 | -0.512 |
| 11 | * | 0.203 | -0.688 | -0.318 |
| 12 | * | 0.296 | -0.456 | -0.209 |
| 13 | * | 0.404 | -0.140 | -0.119 |
| 14 | * | 0.652 | -0.035 | -0.098 |
| 15 | * | 0.671 | 0.261 | -0.040 |
| 16 | * | 0.688 | 0.254 | -0.145 |
| 17 | * | 0.704 | 0.307 | -0.209 |
| 18 | * | 0.720 | 0.319 | -0.192 |
| 19 | * | 0.741 | 0.199 | -0.158 |
| 20 | * | 0.795 | 0.113 | -0.150 |
| 21 | * | 0.824 | 0.130 | -0.168 |
| 22 | * | 0.852 | 0.045 | -0.281 |
| 23 | * | 1.000 | 0.725 | 0.725 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9
FILE NUMBER 48

FLAP DEFLECTION ANGLE = 5

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.062 | -2.268 | -0.158 |
| 2 | * | 0.073 | -2.088 | -0.183 |
| 3 | * | 0.083 | -2.376 | -0.372 |
| 4 | * | 0.094 | -2.194 | -0.471 |
| 5 | * | 0.107 | -1.928 | -0.438 |
| | * | | | |
| 6 | * | 0.123 | -1.997 | -0.533 |
| 7 | * | 0.135 | -2.091 | -0.701 |
| 8 | * | 0.148 | -1.699 | -0.658 |
| 9 | * | 0.163 | -1.338 | -0.488 |
| 10 | * | 0.181 | -1.185 | -0.369 |
| | * | | | |
| 11 | * | 0.203 | -0.754 | -0.215 |
| 12 | * | 0.295 | -0.498 | -0.132 |
| 13 | * | 0.404 | -0.126 | -0.091 |
| 14 | * | 0.652 | -0.002 | -0.081 |
| 15 | * | 0.671 | 0.322 | -0.017 |
| | * | | | |
| 16 | * | 0.688 | 0.384 | -0.286 |
| 17 | * | 0.704 | 0.488 | -0.503 |
| 18 | * | 0.720 | 0.482 | -0.472 |
| 19 | * | 0.741 | 0.316 | -0.327 |
| 20 | * | 0.795 | 0.205 | -0.276 |
| | * | | | |
| 21 | * | 0.824 | 0.214 | -0.275 |
| 22 | * | 0.852 | 0.096 | -0.407 |
| 23 | * | 1.000 | 0.683 | 0.683 |
| | * | | | |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0
FILE NUMBER 40

FLAP DEFLECTION ANGLE = 10

RESULTS OF SEAP DATA

| TAP NUMBER | x/c location | Cp upper | Cp lower |
|---------------|-----------------|-------------|-------------|
| 1 | 0.060 | -1.945 | -0.541 |
| 2 | 0.071 | -1.856 | -0.493 |
| 3 | 0.081 | -2.166 | -0.534 |
| 4 | 0.091 | -2.055 | -0.747 |
| 5 | 0.102 | -1.832 | -0.725 |
| 6 | 0.116 | -1.928 | -0.668 |
| 7 | 0.128 | -2.110 | -0.767 |
| 8 | 0.140 | -1.960 | -0.887 |
| 9 | 0.151 | -1.613 | -0.771 |
| 10 | 0.165 | -1.370 | -0.562 |
| 11 | 0.180 | -1.263 | -0.444 |
| 12 | 0.199 | -0.932 | -0.241 |
| 13 | 0.278 | -0.683 | -0.101 |
| 14 | 0.399 | -0.469 | 0.068 |
| 15 | 0.649 | -0.428 | 0.141 |
| 16 | 0.672 | -0.527 | 0.364 |
| 17 | 0.688 | -0.622 | 0.331 |
| 18 | 0.704 | -0.685 | 0.317 |
| 19 | 0.720 | -0.294 | 0.188 |
| 20 | 0.844 | -0.213 | 0.158 |
| 21 | 0.873 | -0.072 | 0.127 |
| 22 | 0.901 | 0.027 | 0.105 |
| 23 | 1.001 | 0.170 | 0.170 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 41

FLAP DEFLECTION ANGLE = 10

RESULTS OF SERP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.060 | -2.761 | 0.020 |
| 2 | * | 0.071 | -2.588 | 0.006 |
| 3 | * | 0.081 | -2.922 | -0.063 |
| 4 | * | 0.091 | -2.744 | -0.245 |
| 5 | * | 0.102 | -2.430 | -0.265 |
| 6 | * | 0.116 | -2.507 | -0.252 |
| 7 | * | 0.128 | -2.685 | -0.353 |
| 8 | * | 0.140 | -2.476 | -0.469 |
| 9 | * | 0.151 | -2.048 | -0.400 |
| 10 | * | 0.165 | -1.748 | -0.252 |
| 11 | * | 0.180 | -1.617 | -0.168 |
| 12 | * | 0.199 | -1.200 | -0.033 |
| 13 | * | 0.278 | -0.883 | 0.057 |
| 14 | * | 0.399 | -0.588 | 0.165 |
| 15 | * | 0.649 | -0.519 | 0.215 |
| 16 | * | 0.672 | -0.566 | 0.400 |
| 17 | * | 0.688 | -0.671 | 0.377 |
| 18 | * | 0.704 | -0.730 | 0.361 |
| 19 | * | 0.720 | -0.331 | 0.230 |
| 20 | * | 0.844 | -0.247 | 0.199 |
| 21 | * | 0.873 | -0.096 | 0.159 |
| 22 | * | 0.901 | 0.010 | 0.128 |
| 23 | * | 1.001 | 0.165 | 0.165 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 10
 FILE NUMBER 42

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.060 | -3.655 | 0.459 |
| 2 | * | 0.071 | -3.384 | 0.409 |
| 3 | * | 0.081 | -3.737 | 0.327 |
| 4 | * | 0.091 | -3.476 | 0.178 |
| 5 | * | 0.102 | -3.060 | 0.130 |
| | * | | | |
| 6 | * | 0.116 | -3.111 | 0.112 |
| 7 | * | 0.128 | -3.279 | 0.014 |
| 8 | * | 0.140 | -2.999 | -0.100 |
| 9 | * | 0.151 | -2.483 | -0.072 |
| 10 | * | 0.165 | -2.128 | 0.028 |
| | * | | | |
| 11 | * | 0.180 | -1.979 | 0.084 |
| 12 | * | 0.199 | -1.476 | 0.160 |
| 13 | * | 0.278 | -1.090 | 0.209 |
| 14 | * | 0.399 | -0.707 | 0.262 |
| 15 | * | 0.649 | -0.606 | 0.291 |
| | * | | | |
| 16 | * | 0.672 | -0.600 | 0.437 |
| 17 | * | 0.688 | -0.717 | 0.424 |
| 18 | * | 0.704 | -0.771 | 0.407 |
| 19 | * | 0.720 | -0.364 | 0.276 |
| 20 | * | 0.844 | -0.277 | 0.242 |
| | * | | | |
| 21 | * | 0.873 | -0.116 | 0.194 |
| 22 | * | 0.901 | -0.003 | 0.153 |
| 23 | * | 1.001 | 0.163 | 0.163 |
| | * | | | |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9 FLAP DEFLECTION ANGLE = 10
 FILE NUMBER 46

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.060 | -4.614 | 0.771 |
| 2 | * | 0.071 | -4.232 | 0.711 |
| 3 | * | 0.081 | -4.594 | 0.632 |
| 4 | * | 0.091 | -4.240 | 0.517 |
| 5 | * | 0.102 | -3.708 | 0.456 |
| | * | | | |
| 6 | * | 0.116 | -3.724 | 0.417 |
| 7 | * | 0.128 | -3.871 | 0.327 |
| 8 | * | 0.140 | -3.518 | 0.225 |
| 9 | * | 0.151 | -2.909 | 0.221 |
| 10 | * | 0.165 | -2.492 | 0.272 |
| | * | | | |
| 11 | * | 0.180 | -2.326 | 0.301 |
| 12 | * | 0.199 | -1.753 | 0.334 |
| 13 | * | 0.278 | -1.301 | 0.349 |
| 14 | * | 0.399 | -0.833 | 0.359 |
| 15 | * | 0.650 | -0.704 | 0.372 |
| | * | | | |
| 16 | * | 0.672 | -0.668 | 0.488 |
| 17 | * | 0.688 | -0.776 | 0.483 |
| 18 | * | 0.764 | -0.816 | 0.467 |
| 19 | * | 0.720 | -0.398 | 0.330 |
| 20 | * | 0.844 | -0.308 | 0.294 |
| | * | | | |
| 21 | * | 0.873 | -0.135 | 0.237 |
| 22 | * | 0.901 | -0.016 | 0.185 |
| 23 | * | 1.001 | 0.160 | 0.160 |
| | * | | | |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 43

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.073 | -2.507 | -0.227 |
| 2 | * | 0.085 | -2.529 | -0.298 |
| 3 | * | 0.098 | -2.256 | -0.423 |
| 4 | * | 0.114 | -2.350 | -0.409 |
| 5 | * | 0.128 | -2.522 | -0.477 |
| 6 | * | 0.142 | -2.133 | -0.584 |
| 7 | * | 0.157 | -1.715 | -0.457 |
| 8 | * | 0.175 | -1.479 | -0.288 |
| 9 | * | 0.197 | -1.357 | -0.214 |
| 10 | * | 0.222 | -0.903 | 0.011 |
| 11 | * | 0.367 | -0.781 | 0.073 |
| 12 | * | 0.416 | -0.608 | 0.217 |
| 13 | * | 0.607 | -0.616 | 0.254 |
| 14 | * | 0.632 | -0.718 | 0.406 |
| 15 | * | 0.6 | -0.750 | 0.418 |
| 16 | * | 0.674 | -0.945 | 0.444 |
| 17 | * | 0.695 | -1.061 | 0.449 |
| 18 | * | 0.715 | -0.913 | 0.449 |
| 19 | * | 0.735 | -0.269 | 0.248 |
| 20 | * | 0.916 | -0.157 | 0.201 |
| 21 | * | 0.947 | 0.152 | 0.079 |
| 22 | * | 0.977 | 0.247 | 0.083 |
| 23 | * | 1.003 | 0.151 | 0.151 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 44

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.073 | -3.224 | 0.190 |
| 2 | * | 0.085 | -3.193 | 0.103 |
| 3 | * | 0.098 | -2.815 | -0.025 |
| 4 | * | 0.114 | -2.874 | -0.048 |
| 5 | * | 0.128 | -3.036 | -0.129 |
| 6 | * | 0.142 | -2.586 | -0.235 |
| 7 | * | 0.157 | -2.103 | -0.156 |
| 8 | * | 0.175 | -1.819 | -0.041 |
| 9 | * | 0.197 | -1.687 | 0.009 |
| 10 | * | 0.222 | -1.114 | 0.154 |
| 11 | * | 0.367 | -0.959 | 0.193 |
| 12 | * | 0.416 | -0.711 | 0.288 |
| 13 | * | 0.607 | -0.703 | 0.315 |
| 14 | * | 0.631 | -0.762 | 0.439 |
| 15 | * | 0.654 | -0.787 | 0.454 |
| 16 | * | 0.674 | -0.960 | 0.477 |
| 17 | * | 0.695 | -1.061 | 0.481 |
| 18 | * | 0.715 | -0.913 | 0.482 |
| 19 | * | 0.735 | -0.280 | 0.275 |
| 20 | * | 0.916 | -0.166 | 0.224 |
| 21 | * | 0.947 | 0.150 | 0.079 |
| 22 | * | 0.977 | 0.241 | 0.070 |
| 23 | * | 1.003 | 0.143 | 0.143 |

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 45

RESULTS OF SEAP DATA

| TAP NUMBER | * | x/c location | Cp upper | Cp lower |
|---------------|---|-----------------|-------------|-------------|
| 1 | * | 0.073 | -4.040 | 0.539 |
| 2 | * | 0.085 | -3.951 | 0.448 |
| 3 | * | 0.098 | -3.454 | 0.328 |
| 4 | * | 0.114 | -3.475 | 0.280 |
| 5 | * | 0.128 | -3.614 | 0.193 |
| 6 | * | 0.142 | -3.061 | 0.087 |
| 7 | * | 0.157 | -2.491 | 0.121 |
| 8 | * | 0.175 | -2.160 | 0.193 |
| 9 | * | 0.197 | -2.017 | 0.224 |
| 10 | * | 0.222 | -1.329 | 0.296 |
| 11 | * | 0.327 | -1.144 | 0.316 |
| 12 | * | 0.416 | -0.819 | 0.364 |
| 13 | * | 0.607 | -0.792 | 0.382 |
| 14 | * | 0.631 | -0.812 | 0.479 |
| 15 | * | 0.655 | -0.840 | 0.497 |
| 16 | * | 0.674 | -0.997 | 0.518 |
| 17 | * | 0.695 | -1.087 | 0.521 |
| 18 | * | 0.715 | -0.936 | 0.524 |
| 19 | * | 0.735 | -0.292 | 0.311 |
| 20 | * | 0.916 | -0.175 | 0.257 |
| 21 | * | 0.947 | 0.155 | 0.092 |
| 22 | * | 0.977 | 0.246 | 0.069 |
| 23 | * | 1.003 | 0.145 | 0.145 |

ORIGINAL PAGE IS
 OF POOR QUALITY

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 47

RESULTS OF SEAP DATA

| TAP NUMER | * | x/c location | Cp upper | Cp lower |
|--------------|---|-----------------|-------------|-------------|
| 1 | * | 0.073 | -4.897 | 0.791 |
| 2 | * | 0.085 | -4.740 | 0.711 |
| 3 | * | 0.098 | -4.113 | 0.608 |
| 4 | * | 0.114 | -4.090 | 0.548 |
| 5 | * | 0.128 | -4.203 | 0.464 |
| 6 | * | 0.142 | -3.550 | 0.367 |
| 7 | * | 0.157 | -2.891 | 0.365 |
| 8 | * | 0.175 | -2.504 | 0.394 |
| 9 | * | 0.970 | -2.343 | 0.405 |
| 10 | * | 0.222 | -1.500 | 0.424 |
| 11 | * | 0.367 | -1.310 | 0.427 |
| 12 | * | 0.416 | -0.912 | 0.439 |
| 13 | * | 0.607 | -0.874 | 0.450 |
| 14 | * | 0.632 | -0.869 | 0.531 |
| 15 | * | 0.655 | -0.898 | 0.554 |
| 16 | * | 0.674 | -1.044 | 0.574 |
| 17 | * | 0.695 | -1.123 | 0.574 |
| 18 | * | 0.715 | -0.967 | 0.577 |
| 19 | * | 0.735 | -0.304 | 0.356 |
| 20 | * | 0.916 | -0.181 | 0.297 |
| 21 | * | 0.947 | 0.163 | 0.109 |
| 22 | * | 0.977 | 0.253 | 0.070 |
| 23 | * | 1.003 | 0.146 | 0.146 |

```

01: "DELTA P THEORETICAL PRESSURE DISTRIBUTION DATA STORER":
11: dim X(3,3,33),U(3,3,33),L(3,3,33),N$(1),Y$(1)
21: fnt 1,2,2x,f8.5
31: for I=1 to 3
41: for J=1 to 3
51: wrt 4,"ANGLE OF ATTACK=",3(J-1),"DEG"
61: wrt 4,"FLAP DEFLECTION=",5(I-1),"DEG"
71: for K=1 to 33
81: ent "X/C?",X(I,J,K)
91: wrt 4,K,X(I,J,K)
101: next K
111: ent "CHANGES?",N$
121: if cap(N$)="Y"icll 'changes'(1)
131: for K=1 to 33
141: wrt 4.1,K,X(I,J,K)
151: ent "Cp UPPER?",U(I,J,K)
161: wrt 4.1,U(I,J,K);wrt 4
171: next K
181: ent "CHANGES?",N$
191: if cap(N$)="Y"icll 'changes'(2)
201: for K=1 to 33
211: wrt 4.1,K,X(I,J,K),U(I,J,K)
221: ent "Cp LOWER?",L(I,J,K)
231: wrt 4.1,L(I,J,K);wrt 4
241: next K
251: ent "CHANGES?",N$
261: if cap(N$)="Y"icll 'changes'(3)
271: 4+r1
281: wrt r1,"ALPHA=",3(J-1),"DEG"
291: wrt r1,"DELTA FLAP=",5(I-1),"DEG"
301: wrt r1,"X/C Cp UPPER Cp LOWER";wrt r1
311: for K=1 to 33
321: if cap(N$)="Y"icll 6.1,K,X(I,J,K),U(I,J,K),L(I,J,K);wrt r1;jmp 2
331: wrt 4.1,K,X(I,J,K),U(I,J,K),L(I,J,K);wrt r1
341: next K
351: ent "GENERAL CHANGES?",Y$
361: if cap(Y$)="Y"icll "GC"
371: if cap(N$)="Y"icll 4
381: ent "HARD COPY OF THIS?",N$
391: if cap(N$)="Y"icll 3
401: 6+r1;sto 28
411: "N"+N$
421: next J
431: next I
441: trk 1ifdf 33;rcf 33,XI*,U(*),LI*]
451: sto
461: "GC":
471: "N"+Y$
481: ent "CHANGE 1) X/C? 2) Cp UPPER? 3) Cp LOWER?",A
491: cll 'changes'(A)
501: ent "MORE?",Y$
511: if cap(Y$)="Y"icll ret
521: sto 47
531: "changes":
541: "N"+N$
551: ent "NUMBER?",K
561: if pi=1;ent "X/C?",X(I,J,K)
571: if pi=2;ent "Cp UPPER?",U(I,J,K)
581: if pi=3;ent "Cp LOWER?",L(I,J,K)
591: ent "MORE?",N$
601: if cap(N$)="Y"icll ret
611: sto 54
+1442

```

```

01: "SEAP - C SUB P OUTPUTTING PROGRAM      file#s 34+49":
11: dim L$(80),P$(3),Y$(80),S$(10):for S=1 to 60:"*"+L$(S):next S:fd 1
21: dim X(23),U(23),L(23),A,D:"          "L$-L$
31: "          "+S$
41: fnt 1:10x,f3.0,4x,"*",3f15.3
51: fnt 2:9x,"ANGLE OF ATTACK = ",f4.0,10x,"FLAP DEFLECTION ANGLE = ",f4.0
61: fnt 3:9x,"FILE NUMBER  ",f2.0
71: "PCL":ent "FILE NUMBER?",F:if F<34 or F>49:beep:sto +0
81: trk 1:fd F:fd F,X(*),U(*),L(*),A,D
91: "STR":urt 6:"-----":for S=1 to 5:urt 6:next S
101: urt 6:"KANSAS UNIVERSITY FLIGHT RESEARCH LAB":urt 6
111: urt 6:"DELTA P PROJECT - PHASE I"
121: urt 6:
131: urt 6:"SINGLE ELEMENT AIRFOIL PROGRAM RESULTS"
141: urt 6:urt 6:urt 6:urt 6.2:A,D:urt 6.3:F:urt 6:urt 6:L:urt 6
151: urt 6:S$S$S$S$:"RESULTS OF SEAP DATA"
161: urt 6:urt 6:L$
171: urt 6:S$:"TAP  "S$S$  x/c          Cp          Cp"
181: urt 6:S$:"NUMBER +      location      UPPER      lower"
191: urt 6:L$
201: urt 6:"          "+10-B:for S=1 to 23
211: urt 6.1,S:X(S),U(S),L(S):B+1-B
221: if B=5:0-B:urt 6:"          "+"
231: next S:urt 6:"          "+"
241: urt 6:L$:urt 6:urt 6:urt 6
251: for S=1 to 12:urt 6:next S
261: ent "ANOTHER FILE?",P$:if cap(P$)="Y":sto "PCL"
271: sto
*8319

```

C.3 INTERPOLATED CHANGE IN C_p
BY ANGLE OF ATTACK AND
FLAP DEFLECTION

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0 FLAP DEFLECTION ANGLE = 0
 FILE NUMBER 50

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.267 | -1.267 | 0.000 |
| 2 | * | 0.171 | -0.859 | -0.859 | 0.000 |
| 3 | * | 0.223 | -0.588 | -0.588 | 0.000 |
| 4 | * | 0.276 | -0.320 | -0.320 | 0.000 |
| 5 | * | 0.328 | -0.292 | -0.292 | 0.000 |
| 6 | * | 0.380 | -0.264 | -0.264 | 0.000 |
| 7 | * | 0.433 | -0.130 | -0.130 | 0.000 |
| 8 | * | 0.485 | -0.114 | -0.114 | 0.000 |
| 9 | * | 0.537 | -0.111 | -0.111 | 0.000 |
| 10 | * | 0.589 | -0.108 | -0.108 | 0.000 |
| 11 | * | 0.668 | -0.103 | -0.103 | 0.000 |
| 12 | * | 0.720 | -0.075 | -0.075 | 0.000 |
| 13 | * | 0.766 | -0.058 | -0.058 | 0.000 |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 51

FLAP DEFLECTION ANGLE = 0

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.695 | -0.841 | 0.854 |
| 2 | * | 0.171 | -1.162 | -0.574 | 0.587 |
| 3 | * | 0.223 | -0.807 | -0.376 | 0.431 |
| 4 | * | 0.276 | -0.457 | -0.184 | 0.273 |
| 5 | * | 0.328 | -0.419 | -0.164 | 0.255 |
| 6 | * | 0.380 | -0.382 | -0.145 | 0.237 |
| 7 | * | 0.433 | -0.201 | -0.055 | 0.145 |
| 8 | * | 0.485 | -0.177 | -0.049 | 0.127 |
| 9 | * | 0.537 | -0.172 | -0.048 | 0.124 |
| 10 | * | 0.589 | -0.167 | -0.047 | 0.120 |
| 11 | * | 0.668 | -0.160 | -0.045 | 0.115 |
| 12 | * | 0.720 | -0.118 | -0.034 | 0.084 |
| 13 | * | 0.766 | -0.100 | -0.018 | 0.082 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 0
 FILE NUMBER 52

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -2.193 | -0.429 | 1.764 |
| 2 | * | 0.171 | -1.474 | -0.297 | 1.177 |
| 3 | * | 0.223 | -1.031 | -0.165 | 0.866 |
| 4 | * | 0.276 | -0.602 | -0.041 | 0.561 |
| 5 | * | 0.328 | -0.557 | -0.029 | 0.527 |
| 6 | * | 0.380 | -0.511 | -0.018 | 0.493 |
| 7 | * | 0.433 | -0.285 | 0.031 | 0.316 |
| 8 | * | 0.485 | -0.248 | 0.026 | 0.273 |
| 9 | * | 0.537 | -0.240 | 0.025 | 0.265 |
| 10 | * | 0.589 | -0.233 | 0.024 | 0.257 |
| 11 | * | 0.668 | -0.222 | 0.022 | 0.245 |
| 12 | * | 0.720 | -0.163 | 0.017 | 0.180 |
| 13 | * | 0.766 | -0.143 | 0.031 | 0.174 |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
DELTA P PROJECT - PHASE I
SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0 FLAP DEFLECTION ANGLE = 5
FILE NUMBER 53

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.455 | -1.104 | 0.352 |
| 2 | * | 0.171 | -0.973 | -0.809 | 0.165 |
| 3 | * | 0.223 | -0.558 | -0.401 | 0.156 |
| 4 | * | 0.276 | -0.456 | -0.310 | 0.147 |
| 5 | * | 0.328 | -0.358 | -0.216 | 0.142 |
| 6 | * | 0.380 | -0.259 | -0.120 | 0.139 |
| 7 | * | 0.433 | -0.208 | -0.068 | 0.140 |
| 8 | * | 0.485 | -0.196 | -0.054 | 0.142 |
| 9 | * | 0.537 | -0.184 | -0.040 | 0.144 |
| 10 | * | 0.589 | -0.172 | -0.025 | 0.147 |
| 11 | * | 0.668 | -0.049 | 0.177 | 0.226 |
| 12 | * | 0.720 | 0.018 | 0.125 | 0.107 |
| 13 | * | 0.766 | -0.043 | 0.052 | 0.094 |

* Change in pressure coefficient represents the difference
between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 54

FLAP DEFLECTION ANGLE = 5

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.606 | -0.934 | 0.672 |
| | * | | | | |
| 2 | * | 0.171 | -1.078 | -0.704 | 0.374 |
| | * | | | | |
| 3 | * | 0.223 | -0.600 | -0.355 | 0.245 |
| | * | | | | |
| 4 | * | 0.276 | -0.482 | -0.279 | 0.203 |
| | * | | | | |
| 5 | * | 0.328 | -0.360 | -0.207 | 0.154 |
| | * | | | | |
| 6 | * | 0.380 | -0.236 | -0.137 | 0.099 |
| | * | | | | |
| 7 | * | 0.433 | -0.169 | -0.100 | 0.069 |
| | * | | | | |
| 8 | * | 0.485 | -0.152 | -0.090 | 0.061 |
| | * | | | | |
| 9 | * | 0.537 | -0.135 | -0.081 | 0.054 |
| | * | | | | |
| 10 | * | 0.589 | -0.118 | -0.072 | 0.046 |
| | * | | | | |
| 11 | * | 0.668 | 0.085 | 0.055 | -0.030 |
| | * | | | | |
| 12 | * | 0.720 | 0.156 | -0.022 | -0.178 |
| | * | | | | |
| 13 | * | 0.766 | 0.052 | -0.046 | -0.097 |
| | * | | | | |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 5
 FILE NUMBER 55

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.777 | -0.744 | 1.033 |
| 2 | * | 0.171 | -1.164 | -0.589 | 0.575 |
| 3 | * | 0.223 | -0.638 | -0.295 | 0.343 |
| 4 | * | 0.276 | -0.506 | -0.233 | 0.273 |
| 5 | * | 0.328 | -0.362 | -0.182 | 0.180 |
| 6 | * | 0.380 | -0.210 | -0.139 | 0.071 |
| 7 | * | 0.433 | -0.128 | -0.116 | 0.012 |
| 8 | * | 0.485 | -0.106 | -0.112 | -0.006 |
| 9 | * | 0.537 | -0.084 | -0.108 | -0.024 |
| 10 | * | 0.589 | -0.062 | -0.103 | -0.042 |
| 11 | * | 0.668 | 0.211 | -0.050 | -0.261 |
| 12 | * | 0.720 | 0.319 | -0.192 | -0.511 |
| 13 | * | 0.766 | 0.160 | -0.154 | -0.314 |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0 FLAP DEFLECTION ANGLE = 10
 FILE NUMBER 56

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.977 | -0.695 | 1.282 |
| 2 | * | 0.171 | -1.328 | -0.515 | 0.812 |
| 3 | * | 0.223 | -0.856 | -0.198 | 0.658 |
| 4 | * | 0.276 | -0.690 | -0.106 | 0.585 |
| 5 | * | 0.328 | -0.595 | -0.031 | 0.563 |
| 6 | * | 0.380 | -0.503 | 0.042 | 0.545 |
| 7 | * | 0.433 | -0.464 | 0.078 | 0.542 |
| 8 | * | 0.485 | -0.455 | 0.093 | 0.548 |
| 9 | * | 0.537 | -0.447 | 0.108 | 0.555 |
| 10 | * | 0.589 | -0.438 | 0.123 | 0.561 |
| 11 | * | 0.668 | -0.511 | 0.328 | 0.839 |
| 12 | * | 0.720 | -0.294 | 0.188 | 0.482 |
| 13 | * | 0.766 | -0.264 | 0.177 | 0.441 |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3 FLAP DEFLECTION ANGLE = 10
 FILE NUMBER 57

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -2.555 | -0.279 | 2.276 |
| 2 | * | 0.171 | -1.697 | -0.219 | 1.478 |
| 3 | * | 0.223 | -1.104 | -0.006 | 1.098 |
| 4 | * | 0.276 | -0.893 | 0.054 | 0.947 |
| 5 | * | 0.328 | -0.762 | 0.102 | 0.864 |
| 6 | * | 0.380 | -0.635 | 0.149 | 0.783 |
| 7 | * | 0.433 | -0.579 | 0.172 | 0.751 |
| 8 | * | 0.485 | -0.564 | 0.183 | 0.747 |
| 9 | * | 0.537 | -0.550 | 0.193 | 0.743 |
| 10 | * | 0.589 | -0.535 | 0.203 | 0.739 |
| 11 | * | 0.668 | -0.558 | 0.370 | 0.928 |
| 12 | * | 0.720 | -0.331 | 0.231 | 0.562 |
| 13 | * | 0.766 | -0.300 | 0.219 | 0.519 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
DELTA P PROJECT - PHASE I
SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 10
FILE NUMBER 58

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -3.156 | 0.086 | 3.242 |
| 2 | * | 0.171 | -2.070 | 0.050 | 2.119 |
| 3 | * | 0.223 | -1.359 | 0.175 | 1.533 |
| 4 | * | 0.276 | -1.101 | 0.207 | 1.308 |
| 5 | * | 0.328 | -0.932 | 0.230 | 1.162 |
| 6 | * | 0.380 | -0.767 | 0.253 | 1.020 |
| 7 | * | 0.433 | -0.693 | 0.266 | 0.959 |
| 8 | * | 0.485 | -0.672 | 0.272 | 0.944 |
| 9 | * | 0.537 | -0.651 | 0.278 | 0.929 |
| 10 | * | 0.589 | -0.630 | 0.284 | 0.914 |
| 11 | * | 0.668 | -0.601 | 0.413 | 1.014 |
| 12 | * | 0.720 | -0.364 | 0.276 | 0.640 |
| 13 | * | 0.766 | -0.332 | 0.263 | 0.595 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA F PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 0 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 59

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -2.411 | -0.433 | 1.978 |
| | * | | | | |
| 2 | * | 0.171 | -1.526 | -0.322 | 1.204 |
| | * | | | | |
| 3 | * | 0.223 | -0.902 | 0.011 | 0.914 |
| | * | | | | |
| 4 | * | 0.276 | -0.858 | 0.034 | 0.892 |
| | * | | | | |
| 5 | * | 0.328 | -0.814 | 0.056 | 0.870 |
| | * | | | | |
| 6 | * | 0.380 | -0.736 | 0.111 | 0.846 |
| | * | | | | |
| 7 | * | 0.433 | -0.609 | 0.220 | 0.829 |
| | * | | | | |
| 8 | * | 0.485 | -0.611 | 0.230 | 0.841 |
| | * | | | | |
| 9 | * | 0.537 | -0.613 | 0.240 | 0.853 |
| | * | | | | |
| 10 | * | 0.589 | -0.615 | 0.250 | 0.866 |
| | * | | | | |
| 11 | * | 0.668 | -0.882 | 0.436 | 1.318 |
| | * | | | | |
| 12 | * | 0.720 | -0.751 | 0.399 | 1.150 |
| | * | | | | |
| 13 | * | 0.766 | -0.250 | 0.240 | 0.490 |
| | * | | | | |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB

DELTA P PROJECT - PHASE I

SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 3
FILE NUMBER 60

FLAP DEFLECTION ANGLE = 15

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -2.932 | -0.077 | 2.855 |
| 2 | * | 0.171 | -1.882 | -0.067 | 1.816 |
| 3 | * | 0.223 | -1.113 | 0.154 | 1.267 |
| 4 | * | 0.276 | -1.056 | 0.169 | 1.225 |
| 5 | * | 0.328 | -1.001 | 0.183 | 1.183 |
| 6 | * | 0.380 | -0.893 | 0.218 | 1.111 |
| 7 | * | 0.433 | -0.710 | 0.290 | 1.001 |
| 8 | * | 0.485 | -0.708 | 0.298 | 1.006 |
| 9 | * | 0.537 | -0.706 | 0.305 | 1.011 |
| 10 | * | 0.589 | -0.704 | 0.312 | 1.016 |
| 11 | * | 0.668 | -0.908 | 0.470 | 1.378 |
| 12 | * | 0.720 | -0.755 | 0.430 | 1.185 |
| 13 | * | 0.766 | -0.260 | 0.266 | 0.527 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 6 FLAP DEFLECTION ANGLE = 15
 FILE NUMBER 61

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -3.525 | 0.249 | 3.774 |
| 2 | * | 0.171 | -2.234 | 0.177 | 2.411 |
| 3 | * | 0.223 | -1.327 | 0.296 | 1.623 |
| 4 | * | 0.276 | -1.234 | 0.306 | 1.540 |
| 5 | * | 0.328 | -1.140 | 0.317 | 1.457 |
| 6 | * | 0.380 | -0.950 | 0.345 | 1.295 |
| 7 | * | 0.433 | -0.817 | 0.366 | 1.182 |
| 8 | * | 0.485 | -0.809 | 0.371 | 1.180 |
| 9 | * | 0.537 | -0.802 | 0.375 | 1.177 |
| 10 | * | 0.589 | -0.795 | 0.380 | 1.175 |
| 11 | * | 0.668 | -0.947 | 0.511 | 1.459 |
| 12 | * | 0.720 | -0.775 | 0.471 | 1.246 |
| 13 | * | 0.766 | -0.272 | 0.302 | 0.574 |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9 FLAP DEFLECTION ANGLE = 10
 FILE NUMBER 62

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -3.761 | 0.395 | 4.155 |
| 2 | * | 0.171 | -2.426 | 0.284 | 2.709 |
| 3 | * | 0.223 | -1.616 | 0.339 | 1.954 |
| 4 | * | 0.276 | -1.312 | 0.349 | 1.661 |
| 5 | * | 0.328 | -1.108 | 0.353 | 1.461 |
| 6 | * | 0.380 | -0.906 | 0.357 | 1.264 |
| 7 | * | 0.433 | -0.816 | 0.361 | 1.176 |
| 8 | * | 0.485 | -0.789 | 0.363 | 1.152 |
| 9 | * | 0.537 | -0.762 | 0.366 | 1.128 |
| 10 | * | 0.589 | -0.735 | 0.369 | 1.104 |
| 11 | * | 0.668 | -0.675 | 0.467 | 1.141 |
| 12 | * | 0.720 | -0.398 | 0.330 | 0.728 |
| 13 | * | 0.766 | -0.365 | 0.317 | 0.681 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
DELTA P PROJECT - PHASE I
SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9 FLAP DEFLECTION ANGLE = 15
FILE NUMBER 63

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -4.130 | 0.518 | 4.648 |
| 2 | * | 0.171 | -2.590 | 0.388 | 2.978 |
| 3 | * | 0.223 | -1.528 | 0.424 | 1.953 |
| 4 | * | 0.276 | -1.448 | 0.425 | 1.873 |
| 5 | * | 0.328 | -1.369 | 0.426 | 1.795 |
| 6 | * | 0.380 | -1.204 | 0.430 | 1.635 |
| 7 | * | 0.433 | -0.909 | 0.440 | 1.349 |
| 8 | * | 0.485 | -0.898 | 0.443 | 1.341 |
| 9 | * | 0.537 | -0.888 | 0.446 | 1.334 |
| 10 | * | 0.589 | -0.878 | 0.449 | 1.327 |
| 11 | * | 0.668 | -0.998 | 0.568 | 1.566 |
| 12 | * | 0.720 | -0.801 | 0.522 | 1.323 |
| 13 | * | 0.766 | -0.283 | 0.346 | 0.629 |

* Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

ANGLE OF ATTACK = 9 FLAP DEFLECTION ANGLE = 5
 FILE NUMBER 64

RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS

| TAP NUMBER | * | x/c location | Cp upper | Cp lower | change in Cp |
|---------------|---|-----------------|-------------|-------------|-----------------|
| 1 | * | 0.119 | -1.980 | -0.509 | 1.471 |
| | * | | | | |
| 2 | * | 0.171 | -1.270 | -0.435 | 0.835 |
| | * | | | | |
| 3 | * | 0.223 | -0.698 | -0.197 | 0.501 |
| | * | | | | |
| 4 | * | 0.276 | -0.551 | -0.149 | 0.402 |
| | * | | | | |
| 5 | * | 0.328 | -0.385 | -0.120 | 0.266 |
| | * | | | | |
| 6 | * | 0.380 | -0.208 | -0.100 | 0.108 |
| | * | | | | |
| 7 | * | 0.433 | -0.112 | -0.090 | 0.022 |
| | * | | | | |
| 8 | * | 0.485 | -0.086 | -0.088 | -0.002 |
| | * | | | | |
| 9 | * | 0.537 | -0.060 | -0.086 | -0.026 |
| | * | | | | |
| 10 | * | 0.589 | -0.034 | -0.084 | -0.050 |
| | * | | | | |
| 11 | * | 0.668 | 0.271 | -0.027 | -0.298 |
| | * | | | | |
| 12 | * | 0.720 | 0.482 | -0.472 | -0.954 |
| | * | | | | |
| 13 | * | 0.766 | 0.265 | -0.303 | -0.568 |
| | * | | | | |

* Change in pressure coefficient represents the difference
 between lower and upper surface pressure coefficients

```

01: "SEAP INTERPOL. PROG.":
1: dim X(13),U(13),L(13),C(13),A,D:dim G(23),H(23),I(23),O,Q
2: dim E(13,16),R(16),D(16):dim B(4,4),P,X
3: .119*X(1):.171*X(2):.223*X(3):.276*X(4):.328*X(5):.38*X(6):.433*X(7)
4: .485*X(8):.537*X(9):.589*X(10):.668*X(11):.72*X(12):.766*X(13)
5: trk 1:for F=34 to 48
6: ldf F,G(*),H(*),I(*),O,Q
7: for I=1 to 13
8: for J=1 to 22
9: if X(I)#G(J):to 11
10: H(J)+U(I):I(J)+L(I):to 15
11: if not (X(I)>G(J) and X(I)<G(J+1)):to 16
12: (X(I)-G(J))/(G(J+1)-G(J))+Z
13: Z(H(J+1)-H(J))+H(J)+U(I)
14: Z(I(J+1)-I(J))+I(J)+L(I)
15: L(I)-U(I)-C(I)-E(I,F-33)
16: next J
17: next I
18: O+A(F-33)+R(Q+D(F-33)+D
19: rcf F+16,X(*),U(*),L(*),C(*),A,D
20: next F
21: for T=1 to 13:T+P:X(T)+X
22: for S=1 to 16
23: E(T,S)+B(D(S)/5+1,A(S)/3+1)
24: next S
25: fdf T+65:rcf T+65,B(*),P,X
26: next T
*24810

```

ORIGINAL FACE IS
OF POOR QUALITY

```

0: "SEAP - DELTA C SUB P OUTPUTTING PROGRAM      files 50-65"
1: dim L$(80),P$(3),Y$(80),S$(10):for S=1 to 60: L$="" :next S:dim I
2: dim X(13),U(13),L(13),C(13),A,D: " &L$+L$
3: " " +S$
4: fnt 1,10x,f3.0,x,"*",4f12.3
5: fnt 2,9x:"ANGLE OF ATTACK = ",f4.0,10x,"FLAP DEFLECTION ANGLE = ",f4.0
6: fnt 3,9x:"FILE NUMBER ",f2.0
7: "PCL":ent "FILE NUMBER?",F:if F>65 or F<50:to +0
8: trk 1:fd F:ldf F,X(*),U(*),L(*),C(*),A,D
9: "STR":urt 6," -----":for S=1 to 5:urt 6:next S
10: urt 6," KANSAS UNIVERSITY FLIGHT RESEARCH LAB":urt 6
11: urt 6," DELTA P PROJECT - PHASE I"
12: urt 6
13: urt 6," SINGLE ELEMENT AIRFOIL PROGRAM RESULTS"
14: urt 6:urt 6:urt 6:urt 6.2,A,D:urt 6.3,F:urt 6:urt 6:L:urt 6
15: urt 6,S$:"RESULTS OF SEAP DATA INTERPOLATED TO PHASE I TAP LOCATIONS"
16: urt 6:urt 6,L$
17: urt 6,S$:"TAP * x/c Cp Cp change in"
18: urt 6,S$:"NUMBER * location upper lower Cp"
19: urt 6,L$
20: for S=1 to 13
21: urt 6.1,S,N(S),U(S),L(S),C(S):urt 6," *":next S
22: urt 6:L$:urt 6:urt 6:urt 6
23: urt 6,S$:"* Change in pressure coefficient represents the difference"
24: urt 6,S$:" between lower and upper surface pressure coefficients"
25: for S=1 to 12:urt 6:next S
26: ent "another file?":P$:if cap(P$)="#N":to "PCL"
27: stp
*13077

```


C.4 INTERPOLATED CHANGE IN C_p
BY TAP LOCATION

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 1

FILE NUMBER 66

TAP x/c LOCATION 0.119

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---|---------------------------------|-------|-------|-------|
| | | 0 | 3 | 6 | 9 |
| 0.0 | * | 0.000 | 0.854 | 1.764 | 0.000 |
| 5.0 | * | 0.352 | 0.672 | 1.033 | 1.471 |
| 10.0 | * | 1.282 | 2.276 | 3.242 | 4.155 |
| 15.0 | * | 1.978 | 2.855 | 3.774 | 4.648 |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 2

FILE NUMBER 67

TAP x/c LOCATION 0.171

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| ***** | | ***** | | | |
|-------------|---|---------------------------------|-------|-------|-------|
| ***** | | ***** | | | |
| FLAP | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | | 0 | 3 | 6 | 9 |
| ***** | | ***** | | | |
| 0.0 | * | 0.000 | 0.587 | 1.177 | 0.000 |
| 5.0 | * | 0.165 | 0.374 | 0.575 | 0.835 |
| 10.0 | * | 0.812 | 1.478 | 2.119 | 2.709 |
| 15.0 | * | 1.204 | 1.816 | 2.411 | 2.978 |
| | * | | | | |
| ***** | | ***** | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 3

FILE NUMBER 68

TAP x/c LOCATION 0.223

 CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---|---------------------------------|-------|-------|-------|
| | | 0 | 3 | 6 | 9 |
| 0.0 | * | 0.000 | 0.431 | 0.866 | 0.000 |
| 5.0 | * | 0.156 | 0.245 | 0.343 | 0.501 |
| 10.0 | * | 0.658 | 1.098 | 1.533 | 1.954 |
| 15.0 | * | 0.914 | 1.267 | 1.623 | 1.953 |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 4

FILE NUMBER 69

TAP x/c LOCATION 0.276

 CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---------------------------------|-------|-------|-------|
| | 0 | 3 | 6 | 9 |
| 0.0 * | 0.000 | 0.273 | 0.561 | 0.000 |
| 5.0 * | 0.147 | 0.203 | 0.273 | 0.402 |
| 10.0 * | 0.585 | 0.947 | 1.308 | 1.661 |
| 15.0 * | 0.892 | 1.225 | 1.540 | 1.873 |

- *****
- * Results of SEAP data interpolated to phase I tap locations
 - * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 5

FILE NUMBER 70

TAP x/c LOCATION 0.328

 CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---------------------------------|-------|-------|-------|
| | 0 | 3 | 6 | 9 |
| 0.0 * | 0.000 | 0.255 | 0.527 | 0.000 |
| 5.0 * | 0.142 | 0.154 | 0.180 | 0.266 |
| 10.0 * | 0.563 | 0.864 | 1.162 | 1.461 |
| 15.0 * | 0.870 | 1.183 | 1.457 | 1.795 |

- * Results of SEAP data interpolated to Phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 6

FILE NUMBER 71

TAP x/c LOCATION 0.380

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---------------------------------|-------|-------|-------|
| | 0 | 3 | 6 | 9 |
| 0.0 * | 0.000 | 0.237 | 0.493 | 0.000 |
| 5.0 * | 0.139 | 0.099 | 0.071 | 0.108 |
| 10.0 * | 0.545 | 0.783 | 1.020 | 1.264 |
| 15.0 * | 0.846 | 1.111 | 1.295 | 1.635 |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 7

FILE NUMBER 72

TAP x/c LOCATION 0.433

 CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| ***** | | ***** | | | |
|-------------|---|---------------------------------|-------|-------|-------|
| FLAP | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | | 0 | 3 | 6 | 9 |
| ***** | | ***** | | | |
| 0.0 | * | 0.000 | 0.145 | 0.316 | 0.000 |
| 5.0 | * | 0.140 | 0.069 | 0.012 | 0.022 |
| 10.0 | * | 0.542 | 0.751 | 0.959 | 1.176 |
| 15.0 | * | 0.829 | 1.001 | 1.182 | 1.349 |
| | * | ***** | | | |
| ***** | | ***** | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 8

FILE NUMBER 73

TAP x/c LOCATION 0.485

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| | | | | | |
|-------------|---|---------------------------------|-------|--------|--------|
| ***** | | | | | |
| FLAP | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | | 0 | 3 | 6 | 9 |
| ***** | | | | | |
| | * | | | | |
| 0.0 | * | 0.000 | 0.127 | 0.273 | 0.000 |
| | * | | | | |
| 5.0 | * | 0.142 | 0.061 | -0.006 | -0.002 |
| | * | | | | |
| 10.0 | * | 0.548 | 0.747 | 0.944 | 1.152 |
| | * | | | | |
| 15.0 | * | 0.841 | 1.006 | 1.180 | 1.341 |
| | * | | | | |
| ***** | | | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 9

FILE NUMBER 74

TAP x/c LOCATION 0.537

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| ***** | | | | | |
|-------------|---|---------------------------------|-------|--------|--------|
| FLAP * | | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | | 0 | 3 | 6 | 9 |
| ***** | | | | | |
| 0.0 | * | 0.000 | 0.124 | 0.265 | 0.000 |
| 5.0 | * | 0.144 | 0.054 | -0.024 | -0.026 |
| 10.0 | * | 0.555 | 0.743 | 0.929 | 1.128 |
| 15.0 | * | 0.853 | 1.011 | 1.177 | 1.334 |
| | * | | | | |
| ***** | | | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 10

FILE NUMBER 75

TAP x/c LOCATION 0.589

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| | | | | | |
|-------------|---|---------------------------------|-------|--------|--------|
| ***** | | | | | |
| FLAP | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | | 0 | 3 | 6 | 9 |
| ***** | | | | | |
| | * | | | | |
| 0.0 | * | 0.000 | 0.120 | 0.257 | 0.000 |
| | * | | | | |
| 5.0 | * | 0.147 | 0.046 | -0.042 | -0.050 |
| | * | | | | |
| 10.0 | * | 0.561 | 0.739 | 0.914 | 1.104 |
| | * | | | | |
| 15.0 | * | 0.866 | 1.016 | 1.175 | 1.327 |
| | * | | | | |
| ***** | | | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 11

FILE NUMBER 76

TAP x/c LOCATION 0.669

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| ***** | | ***** | | | |
|-------------|---|---------------------------------|--------|--------|--------|
| ***** | | ***** | | | |
| FLAP | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
| DEFLECTION* | * | 0 | 3 | 6 | 9 |
| ***** | | ***** | | | |
| 0.0 | * | 0.000 | 0.115 | 0.245 | 0.000 |
| 5.0 | * | 0.226 | -0.030 | -0.261 | -0.298 |
| 10.0 | * | 0.839 | 0.928 | 1.014 | 1.141 |
| 15.0 | * | 1.318 | 1.378 | 1.459 | 1.566 |
| | * | ***** | | | |
| ***** | | ***** | | | |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 12

FILE NUMBER 77

TAP x/c LOCATION 0.720

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP DEFLECTION* | * | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|---------------------|---|---------------------------------|--------|--------|--------|
| | | 0 | 3 | 6 | 9 |
| 0.0 | * | 0.000 | 0.084 | 0.180 | 0.000 |
| 5.0 | * | 0.107 | -0.178 | -0.511 | -0.954 |
| 10.0 | * | 0.482 | 0.562 | 0.640 | 0.728 |
| 15.0 | * | 1.150 | 1.185 | 1.246 | 1.323 |

- * Results of SEAP data interpolated to phase I tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

KANSAS UNIVERSITY FLIGHT RESEARCH LAB
 DELTA P PROJECT - PHASE I
 SINGLE ELEMENT AIRFOIL PROGRAM RESULTS

TAP NUMBER 13

FILE NUMBER 78

TAP x/c LOCATION 0.766

CHANGE IN PRESSURE COEFFICIENT
 INTERPOLATED

| FLAP | | ALPHA-ANGLE OF ATTACK (degrees) | | | |
|-------------|---|---------------------------------|--------|--------|--------|
| DEFLECTION* | * | 0 | 3 | 6 | 9 |
| ***** | | | | | |
| 0.0 | * | 0.000 | 0.082 | 0.174 | 0.000 |
| 5.0 | * | 0.094 | -0.097 | -0.314 | -0.568 |
| 10.0 | * | 0.441 | 0.519 | 0.595 | 0.681 |
| 15.0 | * | 0.490 | 0.527 | 0.574 | 0.629 |
| | * | | | | |

- * Results of SERP data interpolated to phase 1 tap locations
- * Change in pressure coefficient represents the difference between lower and upper surface pressure coefficients

```


0: "SEAP DATA OUTPUTTING PROGRAM    specific x/c files 66-78"
1: dim L$(80),P$(3),Y$(80),S$(5),T$(10):for S=1 to 75: "+"-L$(S):next S:ind 1
2: dim B(4,4),P,X1"    "+"S$1"    "+"T$
3: fnt 3,z,f12.2,2x:fnt 5.5x:"TAP NUMBER ",f2.0,35x:"FILE NUMBER ",f3.0
4: fnt 4,z,6x,f5.1,2x:"+",2x:fnt 6.5x:"TAP x/c LOCATION ",f6.3
5: T$="0"&T$&" 3"&T$&" 6"&T$&" 9"+Y$
6: "PCL":ent "FILE NUMBER?",F1:if F>79 or F<66:eto +0
7: trk 1:ldf F1:df F,6(4),P,X
8: "STR":urt 6,T$&T$&T$&"-----"ifor S=1 to 8:urt 6:ent S
9: urt 6,T$&"    KANSAS UNIVERSITY FLIGHT RESEARCH LAB":urt 6
10: urt 6,T$&T$&"    DELTA P PROJECT - PHASE I"
11: urt 6
12: urt 6,T$&"    SINGLE ELEMENT AIRFOIL PROGRAM RESULTS"
13: urt 6:urt 6:urt 6:urt 6:urt 6.5,P,F:urt 6:urt 6.6,N:urt 6:urt 6:urt 6
14: urt 6:urt 6,S$&L$&urt 6
15: urt 6,T$&T$&"    CHANGE IN PRESSURE COEFFICIENT"
16: urt 6,T$&T$&T$&"    INTERPOLATED"
17: urt 6:urt 6,S$&L$
18: urt 6,"    FLAP    *    ALPHA-ANGLE OF ATTACK (degrees)"
19: urt 6,"    DEFLECTION+ ",Y$
20: urt 6,S$&L$&urt 6,T$&"    +"
21: for I=1 to 4:(I-1)*C:urt 6.4,C:for J=1 to 4
22: urt 6.3,B(I,J):next J:urt 6:urt 6,T$&"    +"
23: next I
24: urt 6,S$&L$&urt 6:urt 6:urt 6:urt 6:urt 6:urt 6
25: urt 6,T$&"*    Results of SEAP data interpolated to phase I tap locations"
26: urt 6
27: urt 6,T$&"*    Change in pressure coefficient represents the difference"
28: urt 6,T$&"    between lower and upper surface pressure coefficients"
29: for S=1 to 16
30: urt 6:next S:ent "ANOTHER FILE?",P$:if cap(P$)="Y":eto "PCL"
31: end
*8226

```

C.5 GRAPHICAL OUTPUT--FLAP DEFLECTION SENSITIVITY

PRECEDING PAGE BLANK NOT FILMED


NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.1 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. LAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 146 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.2 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 147 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.3 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 148 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C. 4 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HABAK | 8-81 | | | | |
| APPD | | | | | UNIVERSITY OF KANSAS | PAGE 149 |
| APPD | | | | | | |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.5 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAADAK | 8-81 | | | | |
| APPRO | | | | | | |
| APPRO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 150 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C. 6 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. LAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 151 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | |
|----------------------|----------------|---------|------|--|----------------|
| CALC | P. FINN 8-81 | REVISED | DATE | FIGURE C.7 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HRADAK 8-81 | | | | |
| APPO | | | | | |
| APPO | | | | | |
| UNIVERSITY OF KANSAS | | | | | PAGE 152 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.8 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAASAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 153 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.9 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 154 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.10 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRASAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 155 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.11 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRABAK | 8-81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 156 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.12 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 7-8-81 |
| CHECK | R. HRABAM | 8-81 | | | | |
| APPO | | | | | UNIVERSITY OF KANSAS | PAGE 157 |
| APPO | | | | | | |


NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



| | | | | | | |
|----------------------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.13 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - FLAP DEFLECTION SENSITIVITY | DATE 5-8-81 |
| CHECK | A. HADBAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 158 |

C.6 GRAPHICAL OUTPUT--ANGLE OF ATTACK SENSITIVITY


NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.14 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 160 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C. 13 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 161 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.16 <u>SEAP THEORETICAL CHANGE</u> <u>IN PRESSURE COEFFICIENTS</u> <u>- ANGLE OF ATTACK</u> <u>SENSITIVITY</u> | DATE 5-8-81 |
| CHECK | R. HRABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 162 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.17 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY UNIVERSITY OF KANSAS | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | PAGE 163 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|----------------------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.18 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRABAK | 8-81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 164 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.19 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRABAK | 8-81 | | | | |
| API 0 | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 165 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.20 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HARBAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 166 |


NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



ORIGINAL PAGE IS
OF POOR QUALITY


| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.21 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 167 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.22 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. WRABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 168 |

NOTE: THEORETICAL DATA INTERPOLATED TO : SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.23 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 169 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS




| | | | | | | |
|-------|-----------|------|---------|------|--|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.24 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK <u>SENSITIVITY</u> | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 170 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



| | | | | | | |
|----------------------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.25 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 7-8-81 |
| CHECK | R. HAAGAK | 8-81 | | | | |
| APPO | | | | | | |
| APPO | | | | | | |
| | | | | | | |
| UNIVERSITY OF KANSAS | | | | | | PAGE 171 |

NOTE: THEORETICAL DATA INTERPOLATED TO SPECIFIC TAP LOCATIONS



| | | | | | | |
|-------|-----------|------|---------|------|---|----------------|
| CALC | P. FINN | 8-81 | REVISED | DATE | FIGURE C.28 SEAP THEORETICAL CHANGE IN PRESSURE COEFFICIENTS - ANGLE OF ATTACK SENSITIVITY | DATE 5-8-81 |
| CHECK | R. HAABAK | 8-81 | | | | |
| APPD | | | | | | |
| APPD | | | | | | |
| | | | | | UNIVERSITY OF KANSAS | PAGE 172 |

C.7 NUMERICAL REGRESSION DATA

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 66

TAP NUMBER 1

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.137 * -0.127 *      0.97 *
*  3  *  0.152 *  0.523 *      0.84 *
*  6  *  0.165 *  1.218 *      0.70 *
*  9  *  0.318 *  0.247 *      0.86 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.294 * -0.009 *      1.00 *
*  5  *  0.124 *  0.324 *      0.99 *
* 10  *  0.319 *  1.301 *      1.00 *
* 15  *  0.298 *  1.974 *      1.00 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 67

TAP NUMBER 2

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0 *  0.085 * -0.094 *      0.96 *
*  3 *  0.096 *  0.346 *      0.80 *
*  6 *  0.105 *  0.784 *      0.64 *
*  9 *  0.214 *  0.031 *      0.84 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0 *  0.196 * -0.000 *      1.00 *
*  5 *  0.074 *  0.155 *      1.00 *
* 10 *  0.211 *  0.830 *      1.00 *
* 15 *  0.197 *  1.215 *      1.00 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 68

TAP NUMBER 3

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
* alpha * SLOPE * INTERCEPT * COEFFICIENT OF *
* * * * * DETERMINATION *
* * * * *
*****
* 0 * 0.065 * -0.054 * 0.96 *
* 3 * 0.067 * 0.256 * 0.76 *
* 6 * 0.069 * 0.572 * 0.55 *
* 9 * 0.145 * 0.018 * 0.75 *
* * * * *
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
* delta * SLOPE * INTERCEPT * COEFFICIENT OF *
* * * * * DETERMINATION *
* * * * *
*****
* 0 * 0.144 * -0.001 * 1.00 *
* 5 * 0.038 * 0.141 * 0.98 *
* 10 * 0.144 * 0.662 * 1.00 *
* 15 * 0.116 * 0.918 * 1.00 *
* * * * *
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 69

TAP NUMBER 4

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
* alpha * SLOPE * INTERCEPT * COEFFICIENT OF *
* * * * DETERMINATION *
* * * *
*****
* 0 * 0.062 * -0.061 * 0.97 *
* 3 * 0.072 * 0.122 * 0.85 *
* 6 * 0.079 * 0.325 * 0.73 *
* 9 * 0.147 * -0.159 * 0.86 *
* * * *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
* delta * SLOPE * INTERCEPT * COEFFICIENT OF *
* * * * DETERMINATION *
* * * *
*****
* 0 * 0.094 * -0.003 * 1.00 *
* 5 * 0.028 * 0.131 * 0.96 *
* 10 * 0.120 * 0.587 * 1.00 *
* 15 * 0.109 * 0.893 * 1.00 *
* * * *
*****
```


UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 70

TAP NUMBER 5

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *
*  0  *  0.061 * -0.061 *      0.97 *
*  3  *  0.070 *  0.090 *      0.84 *
*  6  *  0.075 *  0.266 *      0.70 *
*  9  *  0.153 * -0.356 *      0.90 *
*      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *
*  0  *  0.088 * -0.003 *      1.00 *
*  5  *  0.013 *  0.125 *      0.84 *
* 10  *  0.100 *  0.564 *      1.00 *
* 15  *  0.102 *  0.869 *      1.00 *
*      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 71

TAP NUMBER 6

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.059 * -0.059 *      0.97 *
*  3  *  0.066 *  0.051 *      0.82 *
*  6  *  0.067 *  0.216 *      0.63 *
*  9  *  0.153 * -0.525 *      0.92 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.082 * -0.003 *      1.00 *
*  5  * -0.004 *  0.122 *      0.31 *
* 10  *  0.080 *  0.544 *      1.00 *
* 15  *  0.085 *  0.840 *      0.99 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 72

TAP NUMBER 7

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.058 * -0.056 *      0.97 *
*  3  *  0.065 *  0.004 *      0.84 *
*  6  *  0.071 *  0.085 *      0.70 *
*  9  *  0.133 * -0.478 *      0.85 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSUS CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.053 * -0.004 *      1.00 *
*  5  * -0.014 *  0.122 *      0.83 *
* 10  *  0.070 *  0.540 *      1.00 *
* 15  *  0.058 *  6.829 *      1.00 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 73

TAP NUMBER 8

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.059 * -0.057 *      0.97 *
*  3  *  0.066 * -0.013 *      0.85 *
*  6  *  0.073 *  0.047 *      0.73 *
*  9  *  0.134 * -0.513 *      0.85 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.046 * -0.003 *      1.00 *
*  5  * -0.017 *  0.124 *      0.86 *
* 10  *  0.067 *  0.547 *      1.00 *
* 15  *  0.056 *  0.841 *      1.00 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 74

TAP NUMBER 9

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.059 * -0.057 *      0.97 *
*  3  *  0.067 * -0.020 *      0.85 *
*  6  *  0.074 *  0.034 *      0.72 *
*  9  *  0.136 * -0.548 *      0.86 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.044 * -0.003 *      1.00 *
*  5  * -0.020 *  0.125 *      0.89 *
* 10  *  0.064 *  0.553 *      1.00 *
* 15  *  0.074 *  0.853 *      1.00 *
*      *      *      *      *
*****
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 75

TAP NUMBER 10

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.060 * -0.058 *      0.97 *
*  3  *  0.068 * -0.027 *      0.85 *
*  6  *  0.074 *  0.020 *      0.72 *
*  9  *  0.138 * -0.583 *      0.87 *
*      *      *      *      *
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.043 * -0.003 *      1.00 *
*  5  * -0.023 *  0.127 *      0.91 *
* 10  *  0.060 *  0.559 *      1.00 *
* 15  *  0.051 *  0.865 *      1.00 *
*      *      *      *      *
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 76

TAP NUMBER 11

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.091 * -0.089 *      0.97 *
*  3  *  0.095 * -0.115 *      0.84 *
*  6  *  0.098 * -0.123 *      0.68 *
*  9  *  0.136 * -1.060 *      0.91 *
*      *      *      *      *
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.041 * -0.003 *      1.00 *
*  5  * -0.060 *  0.180 *      0.92 *
* 10  *  0.033 *  0.831 *      0.99 *
* 15  *  0.027 *  1.306 *      0.98 *
*      *      *      *      *
```

UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 77

TAP NUMBER 12

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.076 * -0.139 *      0.90 *
*  3  *  0.081 * -0.193 *      0.76 *
*  6  *  0.087 * -0.264 *      0.57 *
*  9  *  0.228 * -1.911 *      0.93 *
*      *      *      *      *
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.030 * -0.002 *      1.00 *
*  5  * -0.117 *  0.143 *      0.99 *
* 10  *  0.027 *  0.480 *      1.00 *
* 15  *  0.019 *  1.135 *      0.97 *
*      *      *      *      *
```


UNIVERSITY OF KANSAS
CENTER FOR RESEARCH

DELTA P PROJECT
SEAP

RESULTS OF LINEAR CURVE FITTING

FILE NUMBER 78

TAP NUMBER 13

DELTA (flap deflection angle) versus CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT ANGLES
ANGLES OF ATTACK (alpha)

```
*****
*      *      *      *      *
* alpha *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.036 * -0.016 *      0.91 *
*  3  *  0.039 * -0.035 *      0.64 *
*  6  *  0.042 * -0.059 *      0.41 *
*  9  *  0.120 * -0.949 *      0.72 *
*      *      *      *      *
*****
```

ALPHA (angle of attack) VERSES CHANGE IN
PRESSURE COEFFICIENT AT DIFFERENT FLAP DEFLECTION
ANGLES (delta)

```
*****
*      *      *      *      *
* delta *  SLOPE * INTERCEPT * COEFFICIENT OF *
*      *      *      *      * DETERMINATION *
*      *      *      *      *
*****
*      *      *      *      *
*  0  *  0.029 * -0.002 *      1.00 *
*  5  * -0.073 *  0.109 *      1.00 *
* 10  *  0.027 *  0.439 *      1.00 *
* 15  *  0.015 *  0.485 *      0.99 *
*      *      *      *      *
*****
```

APPENDIX D
THEORETICAL FREQUENCY ANALYSIS DATA

D.1 LOW DYNAMIC PRESSURE

***** DELTA P FREQUENCY ANALYSIS FC1 *****

INPUT DATA

| | |
|--------------------------------------|--------------|
| Wing Area (DC60),ft ² | 174.0000000 |
| Weight (DC71),lb | 2645.0000000 |
| Wing Span (DC72),ft | 35.8000000 |
| MAC (DC73),ft | 4.9000000 |
| Airspeed (DC74),ft/s | 90.9000000 |
| Density (DC75),slugs/ft ³ | 0.0020500 |
| Angle of attack (DC76),rad | 0.0000000 |
| Theta initial (DC77),rad | 0.0000000 |
| Ixxb (DC81),slugs-ft ² | 1346.0000000 |
| CL1 (DC95) | 0.3100000 |
| CD1 (DC96) | 0.0310000 |
| CMT1 (DC97) | 0.0310000 |
| CM1 (DC88) | 0.0000000 |
| CMT1 (DC89) | 0.0000000 |

| Nondimensional derivatives | Dimensional derivatives |
|----------------------------|-------------------------|
|----------------------------|-------------------------|

LONGITUDINAL DERIVATIVES

| | | | |
|--------------|----------|---------------------------|----------|
| CDU (DC11) | 0.0000 | XU (1/s) | -0.0122 |
| CXTU (DC21) | -0.0930 | XTU (1/s) | -0.0061 |
| CDA (DC31) | 0.1300 | XA (ft/st ²) | 3.2267 |
| CDDE (DC41) | 0.0600 | XDE (ft/st ²) | -1.0756 |
| CLU (DC61) | 0.0000 | ZU (1/s) | -0.1223 |
| CLA (DC71) | 4.6000 | ZA (ft/st ²) | -83.0147 |
| CLAD (DC81) | 1.7000 | ZAD (ft/s) | -0.8214 |
| CLO (DC91) | 3.9000 | ZO (ft/s) | -1.8843 |
| CLDE (DC101) | 0.4300 | ZDE (ft/st ²) | -7.7081 |
| CHU (DC121) | 0.0000 | MU (1/st ²) | 0.0000 |
| CMTU (DC131) | 0.0000 | MTU (1/st ²) | 0.0000 |
| CU (1/s) | -0.8900 | MA (1/st ²) | -4.7747 |
| CU (1/s) | 0.0000 | MTA (1/st ²) | 0.0000 |
| CU (1/s) | -5.2000 | MAD (1/s) | -0.7519 |
| CMO (DC171) | -12.4000 | MO (1/s) | -1.7930 |
| CMDE (DC181) | -1.2000 | MDE (1/st ²) | -6.8669 |

 DELTA P FREQUENCY ANALYSIS FC1

TRANSFER FUNCTION POLYNOMIAL COEFFICIENTS

THE COEFFICIENTS OF THE LONGITUDINAL CHARACTERISTIC EQUATION ARE:

A= 91.72136 B= 316.08207 C= 580.02367
 D= 14.18981 E= 18.78257

THE COEFFICIENTS OF THE NUMERATOR U(S) ARE:

CU= 17443.94743 DU= 17156.83612
 0.00000 AU= -98.65111 BU= -363.02499

THE COEFFICIENTS OF THE NUMERATOR ALPHA(S) ARE:

CA= -11.22826 DA= -27.01314
 0.00000 AA= -7.70812 BA= -625.09400

THE COEFFICIENTS OF THE NUMERATOR THETA(S) ARE:

BT= -544.79548 CT= -13.11681
 0.00000 0.00000 AT= -624.04734

STANDARD FORMAT FOR LONGITUDINAL TRANSFER FUNCTIONS:

U(S)/DELTA-E(S) COEFFICIENTS ARE:

KUDE 913.44451
 TU1 1.03184
 TU2 0.06748
 TU3 -0.08258
 OMN SP 2.50357
 ZT SP 0.68689
 OMN P 0.18075
 ZT P 0.01869

ALPHA(S)/DELTA-E(S) COEFFICIENTS ARE:

KALPHADE -1.43820
 TALPHA1 0.01233
 OMN ALPHA 0.20790
 ZT ALPHA 0.04193
 OMN SP 2.50357
 ZT SP 0.68689
 OMN P 0.18075
 ZT P 0.01869

THETA(S)/DELTA-E(S) COEFFICIENTS ARE:

KTHETADE -0.69835
 TTHETA1 40.35522
 TTHETA2 1.17893
 OMN SP 2.50357
 ZT SP 0.68689
 OMN P 0.18075
 ZT P 0.01869

ORIGINAL PAGE IS
 OF POOR QUALITY

D.1.1 WITH PRESSURE SENSOR (PRESSURE COMMAND)

***** DELTA P FREQUENCY ANALYSIS FOR *****

NO. 5: COEFFICIENTS
1.000E 01 5.000E 01
DO. 5: COEFFICIENTS
1.000E 00 1.500E 01 7.000E 01
HI. 5: COEFFICIENTS
6.240E 02 5.448E 02 1.310E 01
DI. 5: COEFFICIENTS
9.170E 01 3.161E 02 5.800E 02 1.420E 01 1.800E 01
ND. 5: COEFFICIENTS
1.000E 00
D2. 5: COEFFICIENTS
1.000E 00

NC0JNC1JDC2J=

6.240E 03 3.665E 04 2.737E 04 6.550E 03
NC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|--------|-----------|
| | 6.240E 03 | 3.665E 04 | 2.737E 04 | 6.550E 03 | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 3 | -0.025 | 0.000 | | ROOT NO. 2 | -5.000 | 0.000 |
| ROOT NO. 1 | -0.348 | 0.000 | | | | |

J = 0.000

DC0JDC1JDC2J+NC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 3.084E 04 | 4.093E 04 | 1.217E 04 |
| | 1.116E 03 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.500 | -3.708 | | ROOT NO. 5 | -7.500 | 3.708 |
| ROOT NO. 4 | -1.720 | -1.819 | | ROOT NO. 3 | -0.000 | -0.111 |
| ROOT NO. 2 | -1.720 | 1.819 | | ROOT NO. 1 | -0.000 | 0.111 |

K = 0.200

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 3.209E 04 | 4.816E 04 | 6.750E 03 |
| | 1.447E 03 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.495 | -3.553 | | ROOT NO. 5 | -7.495 | 3.553 |
| ROOT NO. 4 | -1.663 | -2.043 | | ROOT NO. 3 | -0.066 | -0.170 |
| ROOT NO. 2 | -1.663 | 2.043 | | ROOT NO. 1 | -0.066 | 0.170 |

K = 0.500

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 3.396E 04 | 5.916E 04 | 1.496E 04 |
| | 1.644E 03 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.497 | -3.314 | | ROOT NO. 5 | -7.497 | 3.314 |
| ROOT NO. 4 | -1.588 | -2.374 | | ROOT NO. 3 | -0.119 | -0.116 |
| ROOT NO. 2 | -1.588 | 2.374 | | ROOT NO. 1 | -0.119 | 0.116 |

K = 0.800

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 3.560E 04 | 7.015E 04 | 2.017E 04 |
| | 1.840E 03 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.512 | -3.068 | | ROOT NO. 5 | -7.512 | 3.068 |
| ROOT NO. 4 | -1.520 | -2.692 | | ROOT NO. 3 | -0.121 | 0.000 |
| ROOT NO. 2 | -1.520 | 2.692 | | ROOT NO. 1 | -0.121 | 0.000 |

J= 1.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 3.708E 04 | 7.741E 04 | 1.165E 04 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 1.971E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -7.528 | -2.902 | | ROOT NO. 5 | -1.476 | -2.902 |
| ROOT NO. 4 | -7.528 | 2.902 | | ROOT NO. 3 | -0.000 | -0.000 |
| ROOT NO. 2 | -1.476 | 2.894 | | ROOT NO. 1 | -0.144 | 0.000 |

J= 2.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 4.732E 04 | 1.141E 05 | 5.602E 04 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.626E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -1.253 | -3.784 | | ROOT NO. 5 | -7.671 | 2.011 |
| ROOT NO. 4 | -7.671 | -2.031 | | ROOT NO. 3 | -0.052 | 0.000 |
| ROOT NO. 2 | -1.253 | 3.784 | | ROOT NO. 1 | -0.547 | 0.000 |

K= 3.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 1.056E 04 | 1.508E 05 | 8.339E 04 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 3.281E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -1.021 | -4.491 | | ROOT NO. 5 | -7.865 | 0.902 |
| ROOT NO. 4 | -7.865 | -0.902 | | ROOT NO. 3 | -0.043 | -0.000 |
| ROOT NO. 2 | -1.021 | 4.491 | | ROOT NO. 1 | -0.632 | 0.000 |

K= 4.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 5.580E 04 | 1.874E 05 | 1.108E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 3.936E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -0.797 | -5.067 | | ROOT NO. 5 | -9.423 | 0.000 |
| ROOT NO. 4 | -5.712 | 0.000 | | ROOT NO. 3 | -0.038 | -0.000 |
| ROOT NO. 2 | -0.797 | 5.067 | | ROOT NO. 1 | -0.680 | 0.000 |

K= 5.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 6.204E 04 | 2.241E 05 | 1.381E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 4.591E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -0.589 | -5.551 | | ROOT NO. 5 | -10.280 | 0.000 |
| ROOT NO. 4 | -6.244 | -0.000 | | ROOT NO. 3 | -0.035 | -0.000 |
| ROOT NO. 2 | -0.589 | 5.551 | | ROOT NO. 1 | -0.710 | 0.000 |

K= 6.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 6.828E 04 | 2.607E 05 | 1.655E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 5.246E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -0.396 | -5.971 | | ROOT NO. 5 | -10.901 | 0.000 |
| ROOT NO. 4 | -5.989 | 0.000 | | ROOT NO. 3 | -0.033 | 0.000 |
| ROOT NO. 2 | -0.396 | 5.971 | | ROOT NO. 1 | -0.732 | -0.000 |

K= 7.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 7.452E 04 | 2.974E 05 | 1.929E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 5.901E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -0.213 | -6.344 | | ROOT NO. 5 | -11.403 | -0.000 |
| ROOT NO. 4 | -6.323 | -0.000 | | ROOT NO. 3 | -0.032 | 0.000 |
| ROOT NO. 2 | -0.213 | 6.344 | | ROOT NO. 1 | -0.747 | 0.000 |

K= 8.000
 DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | 9.170E 01 | 1.692E 03 | 1.174E 04 | 8.076E 04 | 3.340E 05 | 2.102E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 6.556E 03 | | | | | |
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 6 | -0.050 | -6.673 | | ROOT NO. 5 | -11.845 | 0.000 |
| ROOT NO. 4 | -6.706 | 0.000 | | ROOT NO. 3 | -0.031 | -0.000 |
| ROOT NO. 2 | -0.050 | 6.673 | | ROOT NO. 1 | -0.759 | -0.000 |

K= 7.000
 DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=
 9.170E 01 1.692E 03 1.174E 04 7.452E 04 2.374E 05 1.125E 05
 5.901E 03

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | -0.218 | -6.344 | ROOT NO. 5 | -11.408 | -0.000 |
| ROOT NO. 4 | -5.823 | -0.000 | ROOT NO. 3 | -0.012 | 0.000 |
| ROOT NO. 2 | -0.218 | 6.344 | ROOT NO. 1 | -0.747 | 0.000 |

K= 8.000
 DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=
 9.170E 01 1.692E 03 1.174E 04 8.076E 04 3.240E 05 2.102E 05
 6.556E 03

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | -0.053 | -6.679 | ROOT NO. 5 | -11.845 | 0.000 |
| ROOT NO. 4 | -5.706 | 0.190 | ROOT NO. 3 | -0.031 | -0.000 |
| ROOT NO. 2 | -0.053 | 6.679 | ROOT NO. 1 | -0.759 | -0.000 |

K= 9.000
 DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=
 9.170E 01 1.692E 03 1.174E 04 8.700E 04 3.707E 05 2.476E 05
 7.211E 03

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 0.102 | -6.986 | ROOT NO. 5 | -12.233 | -0.000 |
| ROOT NO. 4 | -0.031 | 0.000 | ROOT NO. 3 | 0.102 | 6.986 |
| ROOT NO. 2 | -5.618 | 0.000 | ROOT NO. 1 | -0.768 | -0.000 |

K= 10.000
 DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=
 9.170E 01 1.692E 03 1.174E 04 9.324E 04 4.075E 05 2.750E 05
 7.866E 03

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 0.247 | -7.268 | ROOT NO. 5 | -12.584 | -0.000 |
| ROOT NO. 4 | -0.030 | 0.000 | ROOT NO. 3 | 0.247 | 7.268 |
| ROOT NO. 2 | -5.550 | -0.000 | ROOT NO. 1 | -0.776 | -0.000 |

D.1.2 WITHOUT PRESSURE SENSOR (POSITION COMMAND)

 DELTA P THEORETICAL ANALYSIS

N0(S) COEFFICIENTS

1.000E 01

D0(S) COEFFICIENTS

1.000E 00 1.000E 01

M1(S) COEFFICIENTS

6.240E 02 5.448E 02 1.310E 01

D1(S) COEFFICIENTS

9.170E 01 3.161E 02 5.800E 02 1.420E 01 1.890E 01

N2(S) COEFFICIENTS

1.000E 00

D2(S) COEFFICIENTS

1.000E 00

NC0 JNC1 JNC2]=

6.240E 03 5.448E 03 1.310E 02

NC0 JNC1 JNC2]=

6.240E 03 5.448E 03 1.310E 02

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|--------|-----------|
| ROOT NO. 2 | -0.025 | 0.000 | ROOT NO. 1 | -0.848 | 0.000 |

K= 0.000

DC0 JDC1 JDC2]+KNC0 JNC1 JNC2]=

9.170E 01 1.233E 03 3.741E 03 5.814E 03 1.608E 02 1.890E 02

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -1.720 | -1.819 | ROOT NO. 4 | -10.000 | -0.000 |
| ROOT NO. 3 | -0.003 | -0.181 | ROOT NO. 2 | -1.720 | 1.819 |
| ROOT NO. 1 | -0.003 | 0.181 | | | |

K= 0.200

DC0 JDC1 JDC2]+KNC0 JNC1 JNC2]=

9.170E 01 1.233E 03 3.741E 03 7.062E 03 1.250E 03 2.142E 02

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -1.552 | -2.111 | ROOT NO. 4 | -10.167 | 0.000 |
| ROOT NO. 3 | -0.089 | -0.160 | ROOT NO. 2 | -1.552 | 2.111 |
| ROOT NO. 1 | -0.089 | 0.160 | | | |

K= 0.500

DC0 JDC1 JDC2]+KNC0 JNC1 JNC2]=

9.170E 01 1.233E 03 3.741E 03 8.934E 03 2.885E 03 2.535E 02

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -1.345 | -2.504 | ROOT NO. 4 | -10.397 | 0.000 |
| ROOT NO. 3 | -0.180 | -0.021 | ROOT NO. 2 | -1.345 | 2.504 |
| ROOT NO. 1 | -0.180 | 0.021 | | | |

K= 0.800

DC0 JDC1 JDC2]+KNC0 JNC1 JNC2]=

9.170E 01 1.233E 03 3.741E 03 1.081E 04 4.519E 03 2.928E 02

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -1.181 | -2.849 | ROOT NO. 4 | -10.607 | 0.000 |
| ROOT NO. 3 | -0.079 | 0.000 | ROOT NO. 2 | -1.181 | 2.849 |
| ROOT NO. 1 | -0.398 | 0.000 | | | |

K= 1.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 1.205E 04 | 5.609E 03 | 3.190E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | -1.088 | -3.056 | | ROOT NO. 4 | -10.739 | -0.000 |
| ROOT NO. 3 | -0.066 | 0.000 | | ROOT NO. 2 | -1.088 | 3.056 |
| ROOT NO. 1 | -0.466 | 0.000 | | | | |

K= 2.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 1.829E 04 | 1.106E 04 | 4.500E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | -0.728 | -3.892 | | ROOT NO. 4 | -11.317 | 0.000 |
| ROOT NO. 3 | -0.044 | 0.000 | | ROOT NO. 2 | -0.728 | 3.892 |
| ROOT NO. 1 | -0.631 | -0.000 | | | | |

K= 3.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 2.453E 04 | 1.650E 04 | 5.810E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | -0.456 | -4.525 | | ROOT NO. 4 | -11.802 | -0.000 |
| ROOT NO. 3 | -0.037 | -0.000 | | ROOT NO. 2 | -0.456 | 4.525 |
| ROOT NO. 1 | -0.697 | -0.000 | | | | |

K= 4.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 3.077E 04 | 2.195E 04 | 7.120E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | -0.229 | -5.043 | | ROOT NO. 4 | -12.225 | -0.000 |
| ROOT NO. 3 | -0.034 | -0.000 | | ROOT NO. 2 | -0.229 | 5.043 |
| ROOT NO. 1 | -0.732 | -0.000 | | | | |

K= 5.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 3.701E 04 | 2.740E 04 | 8.430E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | -0.029 | -5.485 | | ROOT NO. 4 | -12.603 | 0.000 |
| ROOT NO. 3 | -0.032 | 0.000 | | ROOT NO. 2 | -0.029 | 5.485 |
| ROOT NO. 1 | -0.754 | 0.000 | | | | |

K= 6.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 4.325E 04 | 3.285E 04 | 9.740E 02 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | 0.149 | -5.873 | | ROOT NO. 4 | -12.946 | 0.000 |
| ROOT NO. 3 | -0.031 | 0.000 | | ROOT NO. 2 | 0.149 | 5.873 |
| ROOT NO. 1 | -0.769 | -0.000 | | | | |

K= 7.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 4.949E 04 | 3.830E 04 | 1.105E 03 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | 0.312 | -6.222 | | ROOT NO. 4 | -13.261 | 0.000 |
| ROOT NO. 3 | -0.030 | 0.000 | | ROOT NO. 2 | 0.312 | 6.222 |
| ROOT NO. 1 | -0.780 | -0.000 | | | | |

K= 8.000
 $DE(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$

| | 9.170E 01 | 1.233E 03 | 3.741E 03 | 5.573E 04 | 4.374E 04 | 1.236E 03 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | Real | Imaginary | |
| ROOT NO. 5 | 0.462 | -6.540 | | ROOT NO. 4 | -13.554 | 0.000 |
| ROOT NO. 3 | -0.029 | 0.000 | | ROOT NO. 2 | 0.462 | 6.540 |
| ROOT NO. 1 | -0.798 | 0.000 | | | | |

K= 9.000
 DE 0 JDC 1 JDC 2 J+KNC 0 JNC 1 JNC 2 J=

| | | | | | |
|------------|-----------|-----------|------------|-----------|-----------|
| 9.170E 01 | 1.233E 03 | 3.741E 03 | 6.197E 04 | 4.913E 04 | 1.367E 03 |
| | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 5 | 0.603 | -6.832 | ROOT NO. 4 | -13.829 | -0.000 |
| ROOT NO. 3 | -0.029 | 0.000 | ROOT NO. 2 | 0.603 | 6.832 |
| ROOT NO. 1 | -0.795 | -0.000 | | | |

K= 10.000
 DE 0 JDC 1 JDC 2 J+KNC 0 JNC 1 JNC 2 J=

| | | | | | |
|------------|-----------|-----------|------------|-----------|-----------|
| 9.170E 01 | 1.233E 03 | 3.741E 03 | 6.821E 04 | 5.464E 04 | 1.498E 03 |
| | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 5 | 0.734 | -7.104 | ROOT NO. 4 | -14.087 | -0.000 |
| ROOT NO. 3 | -0.029 | -0.000 | ROOT NO. 2 | 0.734 | 7.104 |
| ROOT NO. 1 | -0.800 | 0.000 | | | |

D.2 HIGH DYNAMIC PRESSURE

***** DELTA P FREQUENCY ANALYSIS FC1 *****

INPUT DATA

| | |
|---|--------------|
| Wing Area (DC80),ft ² | 174.0000000 |
| Weight (DC71),lb | 2645.0000000 |
| Wing Span (DC72),ft | 35.0000000 |
| MAC (DC73),ft | 4.0000000 |
| Airspeed (DC74),ft/s | 372.0000000 |
| Density (DC75),slugs/ft ³ | 0.0020500 |
| Angle of attack (DC76),rad | 0.0000000 |
| Theta initial (DC77),rad | 0.0000000 |
| I _{xx} (DC81),slug-ft ² | 1346.0000000 |
| CL1 (DC95) | 0.3100000 |
| CD1 (DC96) | 0.0310000 |
| CNT1 (DC97) | 0.0310000 |
| CM1 (DC88) | 0.0000000 |
| CNT1 (DC89) | 0.0000000 |

Nondimensional derivatives

Dimensional derivatives

LONGITUDINAL DERIVATIVES

| | | | |
|-------------|----------|--------------------------|-----------|
| CDU (DC1) | 0.0000 | CU (1/s) | -0.0367 |
| CNTU (DC2) | -0.0930 | NTU (1/s) | -0.0183 |
| CDA (DC3) | 0.1300 | CA (ft/s ²) | 29.0610 |
| CDDE (DC4) | 0.0600 | NDE (ft/s ²) | -9.6871 |
| CLU (DC6) | 0.0000 | CU (1/s) | -0.3669 |
| CLA (DC7) | 4.6000 | CA (ft/s ²) | -747.6804 |
| CLAD (DC8) | 1.7000 | CAD (ft/s) | -2.4650 |
| CLO (DC9) | 3.9000 | CO (ft/s) | -5.6549 |
| CLDE (DC10) | 0.4300 | CDE (ft/s ²) | -69.4240 |
| CMU (DC12) | 0.0000 | MU (1/s) | 0.0000 |
| CMTU (DC13) | 0.0000 | MTU (1/s) | 0.0000 |
| CMA (DC14) | -0.8900 | MA (1/s ²) | -42.0034 |
| CMTA (DC15) | 0.0000 | MTA (1/s ²) | 0.0000 |
| CMAD (DC16) | -5.2000 | MAD (1/s) | -2.3565 |
| CMO (DC17) | -12.4000 | MO (1/s) | -5.3809 |
| CMDE (DC18) | -1.2800 | MDE (1/s ²) | -61.8476 |

 DELTA P FREQUENCY ANALYSIS FC1

TRANSFER FUNCTION POLYNOMIAL COEFFICIENTS

THE COEFFICIENTS OF THE LONGITUDINAL CHARACTERISTIC EQUATION ARE:

-- A= 275.26497 B= 2846.82537 C= 15677.67370
 D= 937.76723 E= 507.68751

THE COEFFICIENTS OF THE NUMERATOR U(S) ARE:

0.00000 AU= -2666.51129 BU= -29448.17973
 CU= -96568.06981 DU= 1391743.28340

THE COEFFICIENTS OF THE NUMERATOR ALPHA(S) ARE:

0.00000 AA= -69.42401 BA= -16896.11195
 CA= -910.82371 DA= -730.15732

THE COEFFICIENTS OF THE NUMERATOR THETA(S) ARE:

0.00000 0.00000 AT= -16867.82100
 BT= -44193.19758 CT= -3193.23231

STANDARD FORMAT FOR LONGITUDINAL TRANSFER FUNCTIONS

U(S)/DELTA-E(S) COEFFICIENTS ARE:

KUDE 2741.33843
 TU1 -0.21267
 OMN U 10.53575
 CT U 0.74725
 OMN SP 7.50749
 CT SP 0.68516
 OMN P 0.18090
 CT P 0.15056

ALPHA(S)/DELTA-E(S) COEFFICIENTS ARE:

KALPHADE -1.43820
 TALPHA1 0.00411
 OMN ALPHA 0.20790
 CT ALPHA 0.12923
 OMN SP 7.50749
 CT SP 0.68516
 OMN P 0.18090
 CT P 0.15056

THETA(S)/DELTA-E(S) COEFFICIENTS ARE:

KTHETADE -6.28976
 TTHETA1 13.44681
 TTHETA2 0.39283
 OMN SP 7.50749
 CT SP 0.68516
 OMN P 0.18090
 CT P 0.15056

D.2.1 WITH PRESSURE SENSOR (PRESSURE COMMAND)

 DELTA P FREQUENCY ANALYSIS FC1

N0(S) COEFFICIENTS
 1.000E 01 5.000E 01
 D0(S) COEFFICIENTS
 1.000E 00 1.500E 01 2.295E 02
 N1(S) COEFFICIENTS
 1.687E 04 4.419E 04 3.193E 03
 D1(S) COEFFICIENTS
 2.753E 02 2.847E 03 1.568E 04 9.378E 02 5.077E 02
 N2(S) COEFFICIENTS
 1.000E 00
 D2(S) COEFFICIENTS
 1.000E 00

NC0JNC1JDC2J=

1.687E 05 1.285E 06 2.242E 06 1.597E 05
 NC0JNC1JNC2J=

| | | | | | |
|------------|-----------|-----------|-----------|------------|--------|
| | 1.687E 05 | 1.285E 06 | 2.242E 06 | 1.597E 05 | |
| | | Real | Imaginary | | Real |
| ROOT NO. 3 | -0.074 | 0.000 | | ROOT NO. 2 | -5.000 |
| ROOT NO. 1 | -2.546 | 0.000 | | | 0.000 |

K= 0.000

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 6.976E 03 | 1.216E 05 | 8.894E 05 | 3.613E 06 | 2.228E 05 |
| | 1.165E 05 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.500 | -13.162 | | ROOT NO. 5 | -5.143 | -5.468 |
| ROOT NO. 4 | -7.500 | 13.162 | | ROOT NO. 3 | -5.143 | 5.468 |
| ROOT NO. 2 | -0.027 | -0.179 | | ROOT NO. 1 | -0.027 | 0.179 |

K= 0.200

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 6.976E 03 | 1.216E 05 | 9.232E 05 | 3.870E 06 | 6.712E 05 |
| | 1.484E 05 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -7.129 | -13.026 | | ROOT NO. 5 | -7.129 | 13.026 |
| ROOT NO. 4 | -5.455 | -5.600 | | ROOT NO. 3 | -5.455 | 5.600 |
| ROOT NO. 2 | -0.086 | -0.181 | | ROOT NO. 1 | -0.086 | 0.181 |

K= 0.500

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 6.976E 03 | 1.216E 05 | 9.738E 05 | 4.255E 06 | 1.344E 06 |
| | 1.963E 05 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -6.513 | -12.886 | | ROOT NO. 5 | -5.993 | -5.725 |
| ROOT NO. 4 | -6.513 | 12.886 | | ROOT NO. 3 | -5.993 | 5.725 |
| ROOT NO. 2 | -0.165 | -0.151 | | ROOT NO. 1 | -0.165 | 0.151 |

K= 0.800

DC0JDC1JDC2J+KNC0JNC1JNC2J=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 6.976E 03 | 1.216E 05 | 1.024E 06 | 4.641E 06 | 2.016E 06 |
| | 2.442E 05 | | | | | |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 6 | -5.857 | -12.859 | | ROOT NO. 5 | -6.579 | -5.723 |
| ROOT NO. 4 | -5.857 | 12.859 | | ROOT NO. 3 | -0.234 | -0.059 |
| ROOT NO. 2 | -6.579 | 5.723 | | ROOT NO. 1 | -0.234 | 0.059 |

K= 1.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.058E 06 4.898E 06 2.464E 06
2.762E 05

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|--------|-----------|
| ROOT NO. 6 | -5.428 | -12.910 | ROOT NO. 5 | -6.966 | -5.646 |
| ROOT NO. 4 | -5.428 | 12.910 | ROOT NO. 3 | -0.163 | -0.000 |
| ROOT NO. 2 | -6.966 | 5.646 | ROOT NO. 1 | -0.390 | 0.000 |

K= 2.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.227E 06 6.183E 06 4.706E 06
4.358E 05

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|--------|-----------|
| ROOT NO. 6 | -3.720 | -13.588 | ROOT NO. 5 | -3.720 | 13.588 |
| ROOT NO. 4 | -8.505 | -4.726 | ROOT NO. 3 | -0.107 | 0.000 |
| ROOT NO. 2 | -8.505 | 4.726 | ROOT NO. 1 | -0.784 | 0.000 |

K= 3.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.395E 06 7.469E 06 6.948E 06
5.955E 05

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|--------|-----------|
| ROOT NO. 6 | -2.572 | -14.384 | ROOT NO. 5 | -9.533 | -3.408 |
| ROOT NO. 4 | -2.572 | 14.384 | ROOT NO. 3 | -0.095 | -0.000 |
| ROOT NO. 2 | -9.533 | 3.408 | ROOT NO. 1 | -1.037 | -0.000 |

K= 4.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.564E 06 8.754E 06 9.189E 06
7.552E 05

| | Real | Imaginary | | Real | Imaginary |
|------------|---------|-----------|------------|--------|-----------|
| ROOT NO. 6 | -1.707 | -15.119 | ROOT NO. 5 | -1.707 | 15.119 |
| ROOT NO. 4 | -10.307 | -1.336 | ROOT NO. 3 | -0.090 | -0.000 |
| ROOT NO. 2 | -10.307 | 1.336 | ROOT NO. 1 | -1.223 | -0.000 |

K= 5.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.733E 06 1.004E 07 1.143E 07
9.148E 05

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | -1.007 | -15.788 | ROOT NO. 5 | -13.618 | -0.000 |
| ROOT NO. 4 | -0.087 | 0.000 | ROOT NO. 3 | -1.007 | 15.788 |
| ROOT NO. 2 | -8.258 | -0.000 | ROOT NO. 1 | -1.365 | 0.000 |

K= 6.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 1.902E 06 1.132E 07 1.367E 07
1.074E 06

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | -0.412 | -16.399 | ROOT NO. 5 | -15.408 | 0.000 |
| ROOT NO. 4 | -0.084 | -0.000 | ROOT NO. 3 | -0.412 | 16.399 |
| ROOT NO. 2 | -7.546 | 0.000 | ROOT NO. 1 | -1.478 | -0.000 |

K= 7.000
 $DC(0)DC(1)DC(2)+KNC(0)NC(1)NC(2)=$
2.753E 02 6.976E 03 1.216E 05 2.070E 06 1.261E 07 1.591E 07
1.234E 06

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 0.107 | -16.962 | ROOT NO. 5 | -16.765 | -0.000 |
| ROOT NO. 4 | -0.083 | -0.000 | ROOT NO. 3 | 0.107 | 16.962 |
| ROOT NO. 2 | -7.136 | 0.000 | ROOT NO. 1 | -1.570 | -0.000 |

K= 8.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=
 2.753E 02 6.976E 03 1.216E 05 2.239E 06 1.390E 07 1.816E 07
 1.394E 06

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 0.570 | -17.487 | ROOT NO. 5 | -17.894 | 0.000 |
| ROOT NO. 4 | -0.082 | -0.000 | ROOT NO. 3 | 0.570 | 17.487 |
| ROOT NO. 2 | -6.857 | 0.000 | ROOT NO. 1 | -1.647 | 0.000 |

K= 9.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=
 2.753E 02 6.976E 03 1.216E 05 2.408E 06 1.518E 07 2.040E 07
 1.553E 06

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 0.989 | -17.977 | ROOT NO. 5 | -18.875 | 0.000 |
| ROOT NO. 4 | -0.081 | -0.000 | ROOT NO. 3 | 0.989 | 17.977 |
| ROOT NO. 2 | -6.651 | 0.000 | ROOT NO. 1 | -1.712 | -0.000 |

K= 10.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=
 2.753E 02 6.976E 03 1.216E 05 2.576E 06 1.647E 07 2.264E 07
 1.713E 06

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 6 | 1.373 | -18.439 | ROOT NO. 5 | -19.749 | 0.000 |
| ROOT NO. 4 | -0.080 | 0.000 | ROOT NO. 3 | 1.373 | 18.439 |
| ROOT NO. 2 | -6.490 | -0.000 | ROOT NO. 1 | -1.768 | 0.000 |

D.2.2 WITHOUT PRESSURE SENSOR (POSITION COMMAND)

DELTA F FREQUENCY ANALYSIS

NO(S) COEFFICIENTS

1.000E 01

DO(S) COEFFICIENTS

1.000E 00 1.000E 01

NI(S) COEFFICIENTS

1.687E 04 4.419E 04 3.193E 04

DI(S) COEFFICIENTS

2.753E 02 2.947E 03 1.566E 04 9.827E 02 5.077E 03

N2(S) COEFFICIENTS

1.000E 00

D2(S) COEFFICIENTS

1.000E 00

NEO JNC 1 JNC 2]=

1.687E 05 4.419E 05 3.193E 04

NEO JNC 1 JNC 2]=

1.687E 05 4.419E 05 3.193E 04

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|--------|-----------|
| ROOT NO. 2 | -0.074 | 0.000 | ROOT NO. 1 | -1.546 | 0.000 |

K= 0.000

DEO JDC 1 JDC 2]+KNEO JNC 1 JNC 2]=

2.753E 02 5.600E 03 4.415E 04 1.577E 05 9.886E 03 5.077E 03

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -5.143 | -5.468 | ROOT NO. 4 | -10.000 | 0.000 |
| ROOT NO. 3 | -5.143 | 5.468 | ROOT NO. 2 | -0.027 | -0.179 |
| ROOT NO. 1 | -0.027 | 0.179 | | | |

K= 0.200

DEO JDC 1 JDC 2]+KNEO JNC 1 JNC 2]=

2.753E 02 5.600E 03 4.415E 04 1.915E 05 9.827E 04 1.146E 04

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -4.196 | -5.994 | ROOT NO. 4 | -11.380 | 0.000 |
| ROOT NO. 3 | -0.172 | 0.000 | ROOT NO. 2 | -4.196 | 5.994 |
| ROOT NO. 1 | -0.397 | 0.000 | | | |

K= 0.500

DEO JDC 1 JDC 2]+KNEO JNC 1 JNC 2]=

2.753E 02 5.600E 03 4.415E 04 2.421E 05 2.309E 05 2.104E 04

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -3.209 | -6.779 | ROOT NO. 4 | -12.777 | -0.000 |
| ROOT NO. 3 | -0.102 | -0.000 | ROOT NO. 2 | -3.209 | 6.779 |
| ROOT NO. 1 | -1.044 | 0.000 | | | |

K= 0.800

DEO JDC 1 JDC 2]+KNEO JNC 1 JNC 2]=

2.753E 02 5.600E 03 4.415E 04 2.927E 05 3.634E 05 3.062E 04

| | Real | Imaginary | | Real | Imaginary |
|------------|--------|-----------|------------|---------|-----------|
| ROOT NO. 5 | -2.512 | -7.489 | ROOT NO. 4 | -13.804 | -0.000 |
| ROOT NO. 3 | -0.091 | -0.000 | ROOT NO. 2 | -2.512 | 7.489 |
| ROOT NO. 1 | -1.422 | -0.000 | | | |

K= 1.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 3.264E 05 | 4.518E 05 | 3.701E 04 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | -2.144 | -7.915 | | ROOT NO. 4 | -14.374 | 0.000 |
| ROOT NO. 3 | -0.087 | 0.000 | | ROOT NO. 2 | -2.144 | 7.915 |
| ROOT NO. 1 | -1.592 | 0.000 | | | | |

K= 2.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 4.951E 05 | 8.937E 05 | 6.894E 04 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | -0.869 | -9.619 | | ROOT NO. 4 | -16.508 | 0.000 |
| ROOT NO. 3 | -0.869 | 9.619 | | ROOT NO. 2 | -0.081 | 0.000 |
| ROOT NO. 1 | -2.015 | 0.000 | | | | |

K= 3.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 6.638E 05 | 1.336E 06 | 1.009E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | -0.022 | -10.888 | | ROOT NO. 4 | -18.038 | -0.000 |
| ROOT NO. 3 | -0.079 | 0.000 | | ROOT NO. 2 | -0.022 | 10.888 |
| ROOT NO. 1 | -2.181 | 0.000 | | | | |

K= 4.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 8.324E 05 | 1.778E 06 | 1.328E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | 0.635 | -11.917 | | ROOT NO. 4 | -19.265 | -0.000 |
| ROOT NO. 3 | -0.078 | 0.000 | | ROOT NO. 2 | 0.635 | 11.917 |
| ROOT NO. 1 | -2.268 | 0.000 | | | | |

K= 5.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.001E 06 | 2.220E 06 | 1.647E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | 1.181 | -12.795 | | ROOT NO. 4 | -20.304 | -0.000 |
| ROOT NO. 3 | -0.077 | 0.000 | | ROOT NO. 2 | 1.181 | 12.795 |
| ROOT NO. 1 | -2.322 | 0.000 | | | | |

K= 6.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.170E 06 | 2.661E 06 | 1.967E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | 1.654 | -13.566 | | ROOT NO. 4 | -21.214 | -0.000 |
| ROOT NO. 3 | -0.076 | 0.000 | | ROOT NO. 2 | 1.654 | 13.566 |
| ROOT NO. 1 | -2.358 | 0.000 | | | | |

K= 7.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.338E 06 | 3.103E 06 | 2.286E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | 2.074 | -14.257 | | ROOT NO. 4 | -22.029 | -0.000 |
| ROOT NO. 3 | -0.076 | 0.000 | | ROOT NO. 2 | 2.074 | 14.257 |
| ROOT NO. 1 | -2.384 | 0.000 | | | | |

K= 8.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.507E 06 | 3.545E 06 | 2.605E 05 |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | Real | Imaginary | | | Real | Imaginary |
| ROOT NO. 5 | 2.455 | -14.888 | | ROOT NO. 4 | -22.770 | 0.000 |
| ROOT NO. 3 | -0.076 | 0.000 | | ROOT NO. 2 | 2.455 | 14.888 |
| ROOT NO. 1 | -2.404 | 0.000 | | | | |

K= 9.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.676E 06 | 3.987E 06 | 2.925E 05 |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 5 | 2.803 | -15.468 | | ROOT NO. 4 | -23.452 | -0.000 |
| ROOT NO. 3 | -0.076 | 0.000 | | ROOT NO. 2 | 2.803 | 15.468 |
| ROOT NO. 1 | -2.420 | 0.000 | | | | |

K= 10.000
 DC(0)DC(1)DC(2)+KNC(0)INC(1)INC(2)=

| | | | | | | |
|------------|-----------|-----------|-----------|------------|-----------|-----------|
| | 2.753E 02 | 5.600E 03 | 4.415E 04 | 1.844E 06 | 4.428E 06 | 2.244E 05 |
| | | Real | Imaginary | | Real | Imaginary |
| ROOT NO. 5 | 3.126 | -16.008 | | ROOT NO. 4 | -24.085 | -0.000 |
| ROOT NO. 3 | -0.076 | 0.000 | | ROOT NO. 2 | 3.126 | 16.008 |
| ROOT NO. 1 | -2.432 | 0.000 | | | | |